

**SAFE WORK METHOD STATEMENT**

|                                                                                                                                                                                     |                                                |                                                                                                     |                                                                                                         |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|-----------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| <b>Persons responsible for supervising, inspecting work, work methods, plant &amp; equipment and tools</b>                                                                          | <b>Supervisor/Foreman:</b>                     | <b>Date:</b>                                                                                        |                                                                                                         |
| <b>High Risk Construction Work:</b>                                                                                                                                                 | <b>GENERAL EXCAVATION &amp; TRENCHING</b>      | <b>Project:</b>                                                                                     |                                                                                                         |
| SWMS prepared Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025.<br>SWMS Review Date: April 2026 unless required earlier |                                                | <b>Location:</b>                                                                                    |                                                                                                         |
| <b>Approval to use this SWMS:</b> "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"           |                                                |                                                                                                     |                                                                                                         |
| John Guy<br><b>Name</b>                                                                                                                                                             | Director - Paneltec Pty Ltd<br><b>Position</b> | 0408 449 023<br> | <br><b>Signature</b> |
|                                                                                                                                                                                     |                                                |                                                                                                     | 31/08/2025 - V12.0<br><b>Date</b>                                                                       |

**RISK MATRIX**

| Level                                  | Description of Consequence or Impact                                                                                                                                                              | Consequence              | Likelihood / Probability |                      |                      |
|----------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|--------------------------|----------------------|----------------------|
|                                        |                                                                                                                                                                                                   |                          | L<br><i>Likely</i>       | M<br><i>Moderate</i> | U<br><i>Unlikely</i> |
| H (1)<br><i>(High level of harm)</i>   | Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.                    | H (1)<br><i>(High)</i>   | 1                        | 1                    | 2                    |
| M (2)<br><i>(Medium level of harm)</i> | Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.                  | M (2)<br><i>(Medium)</i> | 1                        | 2                    | 3                    |
| L (3)<br><i>(Low level of harm)</i>    | Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm. | L (3)<br><i>(Low)</i>    | 2                        | 3                    | 3                    |
| <b>Level</b>                           | <b>Likelihood / Probability</b>                                                                                                                                                                   |                          |                          |                      |                      |
| Likely                                 | Could happen frequently                                                                                                                                                                           |                          |                          |                      |                      |
| Moderate                               | Could happen occasionally                                                                                                                                                                         |                          |                          |                      |                      |
| Unlikely                               | May occur only in exceptional circumstances                                                                                                                                                       |                          |                          |                      |                      |

**HIERARCHY OF RISK CONTROL**

The hierarchy of controls must be applied in the order below for all identified hazards.

|                                                                                                           |
|-----------------------------------------------------------------------------------------------------------|
| <b>Level 1</b><br>Eliminate the hazard                                                                    |
| <b>Level 2</b><br>Substitute the hazard with something safer.                                             |
| <b>Level 3</b><br>Isolate the hazard from people.<br>Reduce the risks through engineering controls.       |
| <b>Level 4</b><br>Reduce exposure to the hazard using administrative actions.                             |
| <b>Level 5</b><br>Use personal protective equipment                                                       |
| The control measures that you put in place should be reviewed regularly to make sure they work as planned |

**ACTIVITY ANALYSIS**

| Steps in Activity           | Potential Hazards                                                                                                         | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                  | Responsible Person/s   | Risk Class After Controls In Place |
|-----------------------------|---------------------------------------------------------------------------------------------------------------------------|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------------------------------|
| Training                    | To prevent injuries or illness to workers                                                                                 | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Machinery operators will have the necessary current licence for the equipment they will operate.</li> <li>2. All persons will have a current construction induction card.</li> </ol>                                                                                                                                                                                                                        | Supervisor<br>All      | <b>2</b>                           |
| Arriving on site            | Entry unsafe or unauthorised areas                                                                                        | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Report to site office for site induction if required.</li> <li>2. Risk assessment of site conditions and Site-specific induction &amp; toolbox meeting to be conducted.</li> <li>3. Consider all environmental protection issues and the impact caused by entry to site.</li> </ol>                                                                                                                         | All<br>Supervisor      | <b>2</b>                           |
| Unloading Plant & equipment | <p>Falls, slips &amp; trips from vehicle, trucks and floats</p> <p>Machinery plant tipping over or falling from ramps</p> | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Ensure all vehicles are parked in a clear level area for unloading plant and equipment.</li> <li>2. Extra care taken in wet conditions, use a ramp to load and unload plant.</li> <li>3. Persons unloading equipment to wear seat belt.</li> <li>4. Operators familiar with SWMS – Loading &amp; Unloading Plant &amp; Equipment.</li> <li>5. Only suitably trained personnel to work with plant</li> </ol> | Operator               | <b>2</b>                           |
|                             | Electrocution                                                                                                             | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Be aware of overhead power lines</li> </ol>                                                                                                                                                                                                                                                                                                                                                                 | Operator               | <b>2</b>                           |
|                             | Traffic hazards, hit by vehicles or other on-site plant and equipment                                                     | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Ensure hazard &amp; warning signage is in place as required when unloading plant.</li> <li>2. Training in the use of PPE equipment such as fluorescent safety vests/clothing.</li> </ol>                                                                                                                                                                                                                    | Operator<br>Supervisor | <b>2</b>                           |
|                             | Hand, foot & hearing damage, crushing of limbs                                                                            | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Training in manual handling &amp; the correct protection, gloves and safety footwear.</li> </ol>                                                                                                                                                                                                                                                                                                            | Supervisor             | <b>3</b>                           |
| Machine Pre Start Check     | Unsafe working conditions. Potential for accident.                                                                        | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Equipment Prestart checklist forms filled out &amp; defects documented, supervisor notified.</li> <li>2. Ensure windows/ mirrors are clean.</li> <li>3. Ensure all controls are in neutral or park.</li> <li>4. Ensure all gear in the cabin is correctly stored.</li> <li>5. Adjust the seat and use the seat belt.</li> </ol>                                                                             | Operator               | <b>2</b>                           |
| Machine Starting checks     | Unsafe working conditions. Increased likelihood of accident during operation.                                             | <b>1</b>   | <ol style="list-style-type: none"> <li>1. The operator must be seated and in full control of the machine when starting.</li> <li>2. Check the operation of all of the controls and gauges.</li> </ol>                                                                                                                                                                                                                                                 | Operator               | <b>2</b>                           |

| Steps in Activity                              | Potential Hazards                             | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Responsible Person/s                                  | Risk Class After Controls In Place |
|------------------------------------------------|-----------------------------------------------|------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------|
|                                                |                                               |            | 3. Listen and watch for defects.<br>4. Test hydraulic functions.<br>5. Ensure all grounded attachments are safely retracted<br>6. Test lights, horn and travel alarm.<br>7. Check safety locking pins in quick hitch are locked for buckets or attachments.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                                       |                                    |
| Set out work area and check excavation levels. | Struck by road or construction plant.         | <b>1</b>   | 1. Barricade area off or sign appropriately to restrict access and minimise plant working area.<br>2. All workers to wear safety vests.<br>3. Operational flashing lights and reversing beepers.<br>4. All trenches greater than 1.5 metres in depth are to be appropriately benched, battered or shored, or otherwise protected from collapse. (e.g. refer Safety Alert-'Trench shield Guards', or the operator/supervisor is to have on-site an authorised geotechnical report from a n engineer confirming that the soil is cohesive and safe).                                                                                                                                                                                                                                                                                                                                                              | Supervisor<br><br>All Operator                        | <b>2</b>                           |
|                                                | Striking underground services - electrocution | <b>1</b>   | 1. Before digging starts, make sure you know the exact location of any underground electrical cables, gas lines, water, sewerage and telecommunications cables<br>2. Do not rely solely on site-plans and drawings as these are sometimes not accurate or complete.<br>3. Seek assistance from the local services and distribution companies.<br>4. Use "Before You Dig Australia" - <a href="http://www.BYDA.com.au">www.BYDA.com.au</a> to make an enquiry.<br><b>Emergency Procedure to be used:</b><br>➤ If the contact point between the plant and the live power is under the ground, there is an area around that point which can be electrified.<br>➤ Jump well clear of that point and move away from the machine and warn others to keep away<br>➤ Stay near the site until help arrives<br>➤ Report the incident to your supervisor immediately who may need to report to Workcover or Tas Networks. | Supervisor<br><br><br><br><br><br><br><br><br><br>All | <b>2</b>                           |

| Steps in Activity                                                     | Potential Hazards                                                                                                                                        | Risk Class | 1. Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                      | Responsible Person/s         | Risk Class After Controls In Place |
|-----------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|------------------------------------|
|                                                                       | Persons falling or tripping over on site.                                                                                                                | <b>2</b>   | 2. Maintain good house keeping.<br>3. Barricade off unsafe areas.<br>4. Clearly mark protruding objects using paint, caps or hazard tape.                                                                                                                                                                                                                                                                                    | All Supervisor<br>Supervisor | <b>3</b>                           |
|                                                                       | Dust entering eyes                                                                                                                                       | <b>2</b>   | 1. Suppress dust using water truck.<br>2. Eye protection to be worn when required.                                                                                                                                                                                                                                                                                                                                           | Supervisor<br>All            | <b>3</b>                           |
| Excavator operation                                                   | Engine failure                                                                                                                                           | <b>2</b>   | 1. Warm up engine and hydraulic oil for a few minutes before starting work.                                                                                                                                                                                                                                                                                                                                                  | Operator                     | <b>3</b>                           |
| Clearing & grubbing<br>Excavation<br>placement and<br>compaction fill | Striking other objects whilst slewing excavator, materials on the ground flicking up as excavator travels over site.<br>Overbalance of machine at reach. | <b>1</b>   | 1. Be aware of what obstacles are around the site especially when slewing excavator.<br>2. Assess what weights the machine can handle at reach safely before attempting to load trucks.<br>3. Do not carry passengers.<br>4. Keep machine under control at all times.<br>5. Carry the bucket as close to the ground as possible whilst traveling.<br>6. Travel & operate at a safe speed for the operation being undertaken. | Operator                     | <b>2</b>                           |
|                                                                       | Attachments or bucket disconnecting from hitch.                                                                                                          | <b>1</b>   | 1. Ensure quick hitch safety pins are engaged whilst bucket or attachments are engaged into quick hitch.                                                                                                                                                                                                                                                                                                                     | Operator                     | <b>2</b>                           |
|                                                                       | Release of hydraulic hoses when changing work implements such as tilt bucket, pulverisor, rockbreaker and compaction plate.                              | <b>1</b>   | 1. Ensure hydraulic pressure is taken off hydraulic hoses before releasing couplings. Pressure is normally released if engine is shut down and work tool pedal is pressed back & forth or two way flow ball valve is switched off.                                                                                                                                                                                           | Operator                     | <b>2</b>                           |
|                                                                       | Uncontrolled slippage                                                                                                                                    | <b>1</b>   | 1. Assess ground surface conditions eg; wet ground conditions, steep slope.<br>2. When working on top of mound make sure excavator is not taken too close to the edge.                                                                                                                                                                                                                                                       | Operator                     | <b>2</b>                           |

| Steps in Activity | Potential Hazards                                                                 | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Responsible Person/s       | Risk Class After Controls In Place |
|-------------------|-----------------------------------------------------------------------------------|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|------------------------------------|
|                   | Rockbreaker & pulverizer operation<br>Flying fragments or reo steel from concrete | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Be aware that fragments can fly from chisel of the rockbreaker, and pulverizer .</li> <li>2. Whilst operating excavator be aware that demolition debris such as reo. and pipe etc... can be flicked up by the tracks and could hit a worker or machine.</li> <li>3. Use eye &amp; hearing protection &amp; keep others well away from work area.</li> </ol>                                                                                                                                                                                                                      | Operator                   | <b>2</b>                           |
|                   | Rock & log grab                                                                   | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Material or objects lifted can become insecure due to crumbling or breaking be aware of the different hydraulic pressures that can be applied to objects</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                              | Operator                   | <b>3</b>                           |
|                   | Compaction plate                                                                  | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Be aware that vibration can affect nearby buildings or unstable ground or trench walls &amp; excavations.</li> <li>2. Assess the situation &amp; surrounding areas that may be affected.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                              | Operator                   | <b>3</b>                           |
|                   | Striking overhead services- electrocution                                         | <b>1</b>   | <p>Operators need to keep;</p> <ol style="list-style-type: none"> <li>1. At least 3 metres from 132,000 volt lines.</li> <li>2. At least 6 metres from 132,000 to 330,000volt lines.</li> <li>3. Areas closer than 3m are no go zone.</li> <li>4. Use certified spotter if working near powerlines.</li> <li>5. (3m to 6.4m).</li> <li>6. Clarify safe working distances with site manager.</li> <li>7. If in doubt of line voltage keep at least 8 metres away.</li> </ol> <p><b>If your machine makes contact with electrical wires- Refer to Emergency Procedures below and the A5 laminated card in the cabin.</b></p> | Operator<br><br>Supervisor | <b>2</b>                           |

| Steps in Activity | Potential Hazards            | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Responsible Person/s                                                     | Risk Class After Controls In Place |
|-------------------|------------------------------|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|------------------------------------|
|                   |                              |            | <b>Overhead Wires – Emergency Procedure</b><br>1. Stay calm.<br>2. Do not leave your seat.<br>3. Warn others to stay away.<br>4. If possible, try to break contact with the wires, if possible try to lower the bucket without causing further damage to the power lines.<br>5. Make sure that the bucket does not make contact with the ground as this could earth the machine.<br>6. Phone emergency services to have power turned off.<br>If it is unsafe to stay in/on the machine because the machine is in danger, such as from fire or if you are alone.<br>1. <b>Jump well clear onto dry ground if possible, making sure you have both legs together and shuffle with feet together or hop (eg ; kangaroo hop) and hop at least 10 metres away from the machine.</b> |                                                                          |                                    |
|                   |                              |            | 2. Do not climb down because if you make contact with the machine and the ground at the same time you could be electrocuted.<br>3. If the contact point is under the ground, there is an area around that point which can be electrified.<br>4. Jump well clear of that point and move away from the machine and warn others to keep away.<br>5. Stay near the site until help arrives.<br>6. Report the incident to your supervisor immediately who may need to report to Workcover or Tas Networks.                                                                                                                                                                                                                                                                         |                                                                          |                                    |
|                   | Striking personnel and plant | <b>1</b>   | 1. Hold toolbox meeting to discuss hazards.<br>2. Reflective safety vests to be worn at all times.<br>3. Where possible minimise plant & personnel in work areas.<br>4. Separate trafficable areas.<br>5. Install giveaway and stop signs where necessary.<br>6. Excavator to have operational flashing light and reversing beeper.                                                                                                                                                                                                                                                                                                                                                                                                                                           | Supervisor<br>All<br>Supervisor<br>Supervisor<br>Supervisor<br>Operators | <b>2</b>                           |

| Steps in Activity | Potential Hazards                                                      | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Responsible Person/s                     | Risk Class After Controls In Place |
|-------------------|------------------------------------------------------------------------|------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|------------------------------------|
|                   | Exposure to noise                                                      | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Suppress noise using mufflers.</li> <li>2. Ear protection must be worn by personnel working near noisy equipment.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                | Workshop<br>All                          | <b>3</b>                           |
|                   | Ground failure leading to machine rollover and personnel being crushed | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Only competent operators to use machinery.</li> <li>2. Operator to complete visual assessment of ground conditions.</li> <li>3. All unbattered excavations to be barricaded off.</li> <li>4. Do not operate close to an overhang or a deep ditch or excavation the weight could collapse the sides of the trench.</li> <li>5. Always approach embankments or trenches from a 90 degree angle.</li> <li>6. Do not use the bucket as a hammer.</li> <li>7. When working on a slope determine whether to dump the spoil on the high side or low side of the trench.</li> </ol> | Supervisor<br>Operator<br><br>Supervisor | <b>2</b>                           |
| Lifting           | Sling failure                                                          | <b>1</b>   | <ol style="list-style-type: none"> <li>1. The Working Load Limit (<b>WLL</b>) of the machine should be marked on the machine</li> <li>2. Do not exceed the <b>WLL</b> and work radius limits of the machine.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                               | Operator                                 | <b>2</b>                           |

| Steps in Activity                                        | Potential Hazards                              | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Responsible Person/s | Risk Class After Controls In Place |
|----------------------------------------------------------|------------------------------------------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
|                                                          | Struck by moving load/part                     | <b>1</b>   | 1. Check the <b>WLL</b> of the machine and the lifting lugs, slings & chains to ensure the load is correctly slung and balanced and is within the <b>WLL</b> .                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Operator             | <b>2</b>                           |
|                                                          | Ground failure                                 | <b>1</b>   | 1. If there is any sign of instability lower the load immediately.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Operator             | <b>2</b>                           |
|                                                          | Failure during lifting                         | <b>1</b>   | 1. When the load is raised keep all people at a safe distance.<br>2. Do not swing loads over people's heads.<br>3. Do not leave the load suspended in the air. Lower it as soon as possible.<br>4. Always lower the load to the ground if leaving the machine.<br>5. Make allowances for materials when they are wet. They will weigh more than normal.<br>6. If you do not know the weight of the load do not lift.<br>7. When working on sloping or flat surfaces be aware of the safe bucket capacity eg; rocks falling from an overfull bucket and damaging other items or persons.<br>8. Do not reeve or nip slings around buckets as the sling can be cut by the cutting edge or teeth of the bucket.<br>9. Do not place a sling over a tooth or teeth.<br>10. Place the lifting hook onto the approved lifting lug normally attached to the quick hitch.<br>11. The person who slings and directs the load must have a dogman's certificate.<br>12. Inspect all slings prior to use. Are they serviceable?<br>13. Refer to SWMS – Using Powered Earthmoving Equipment as a Crane. | Operator             | <b>2</b>                           |
| Traveling equipment on roadway , private or public areas | Damage to roadway or public / private property | <b>2</b>   | 1. Check ownership of properties or boundaries.<br>2. Travel machine as to avoid disturbance to roadway or public or private lands eg; lift one track of an excavator to turn on undisturbed areas if required, avoid sharp turns on roadways.<br>3. Be aware of what damage the tracks can do to surfaces.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Operator             | <b>3</b>                           |
| Equipment shut down                                      | Personnel struck by rolling plant              | <b>1</b>   | 1. Assess parking area as to site vision for other works in the area (eg traffic situation on roadworks site, avoid parking where vision is blocked).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Operator             | <b>2</b>                           |



| Steps in Activity           | Potential Hazards                                                          | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Responsible Person/s | Risk Class After Controls In Place |
|-----------------------------|----------------------------------------------------------------------------|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
|                             |                                                                            |            | 2. Park on firm, level ground where possible.<br>3. Park the machine up and down the slope when parking on a grade.<br>4. Park in a non-operating area.<br>5. Park away from deep excavations and trenches.<br>6. Place the hydraulic lock mechanism in the lock position.<br>7. Lower the bucket or attachment to the ground.<br>8. Idle the engine for gradual cooling before turning it off.<br>9. Move the steering levers back and forward and cycle the hydraulic controls to dissipate residual pressure in the hydraulic system before leaving the machine.<br>10. Remove the ignition key and secure the machine. |                      |                                    |
| <b>Environmental Issues</b> | Transmission of material off site to public domain eg mud or to main road. | <b>2</b>   | 1. Where possible endeavor to not park in muddy areas.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Operator             | <b>3</b>                           |
|                             | Hydraulic oil spill                                                        | <b>3</b>   | 1. Make sure there is a visual check of all hydraulic hoses is part of your prestart check.<br>2. Should there be an extensive oil leak- clean it up immediately.                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Operator             | <b>3</b>                           |

**Trenching & Excavation Checklist** (Ref: WorkCover)

**1. Have all underground services been located?** Before digging starts, make sure you know the exact location of any underground electrical cables, gas lines, water, sewerage and telecommunications cables. Do not rely solely on site-plans and drawings as these are sometimes not accurate or complete. Seek assistance from the local services and distribution companies.

**2. Is earthmoving plant being used safely?** Check that plant operators are appropriately qualified. Look for qualifications endorsed with LL (for front-end loaders), LB (for front-end loader /backhoes), LS (for skid-steer loaders), LE (for excavators), LD (for draglines) or LZ (for dozers). Old-style pre-national certificates can also be used. Make the operators show you their qualifications and keep an on-site register. Make sure all earthmoving plant is properly maintained and fully serviceable. Check that operators are not undermining existing buildings or temporary structures such as scaffolds and falsework. Make sure spoil is being kept at least a half metre back from the edge of trenches and that earthmoving plant is a safe distance from the edge of excavations. Make sure unattended front-end loaders, backhoes and excavators are always left with the bucket fully lowered to the ground. When parked overnight alongside roads or on other public space, make sure earthmoving plant is locked up and barricaded with warning lamps to alert traffic.

**3. Are workers protected from trench collapse?** Never allow workers to enter a trench or shaft which is greater than 1.5 metres deep unless it has been safely benched and battered back, or it has been properly shored, or the workers are fully protected within a trench shield. Shoring should be positioned and fixed from above; never from below. All timber used in ground support should be at least F8 grade hardwood. Never use softwood because this can fail suddenly without warning, whereas hardwood will start to creak loudly when it is becoming overloaded, warning workers to leave the trench immediately. Make sure all workers in excavations always wear safety helmets.

**4. Are confined space precautions needed?** Where there is any possibility of a hazardous atmosphere within an excavation, the extra precautions for entry into confined spaces must be put in place.

**5. Are people safeguarded from falling into excavations?** Make sure trenches, shafts and excavations are properly barricaded, covered or isolated to prevent people falling into them. Whenever an excavation is to be left unattended, make sure it is secured to prevent children or other people from wandering into danger.

**6. Is there safe access and egress to trenches and shafts?** Never allow workers to climb up and down the soldier sets used in trench shoring, because they can loosen or damage the support system, triggering a trench collapse. Make sure industrial-grade portable ladders are used to gain access to and from the excavation floor.

**7. Is someone else always present when a worker is below ground?** Never allow anyone to work alone in a trench or shaft. Make sure there is always another person close by who can provide help or get help if necessary.

**8. Are open excavations being regularly inspected?** The condition of soil surrounding trenches and shafts can change quickly due to the soil drying out, movement of heavy plant close to the excavation, changes in the water table or water saturation of the soil. Make sure the soil condition and the state of shoring, benching and battering and trench walls is frequently checked for signs of earth fretting, slipping, slumping or ground swelling. Where necessary, repair the excavation or strengthen the shoring system from above before allowing work below ground to continue.

| <b>ENVIRONMENTAL RISK ASSESSMENT &amp; CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY</b> |                                                                                                                                                                                                               |                   |                                                                                                                                                                                                                                                                                                                                                                                        |                             |                                           |
|--------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|-------------------------------------------|
| <b>Work Activity Risk</b>                                                                                          | <b>Hazard</b>                                                                                                                                                                                                 | <b>Risk Class</b> | <b>Risk Control Measure</b>                                                                                                                                                                                                                                                                                                                                                            | <b>Responsible Person/s</b> | <b>Risk Class after Controls in place</b> |
| <b>Emergencies</b>                                                                                                 | Accident/ Incident<br>Fire<br>Spill                                                                                                                                                                           | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring.</li> <li>2. Emergency numbers available on site.</li> <li>3. Fire Extinguishers/First Aid Kits/Spill Kits on site.</li> </ol>                                                                                                         | Supervisor<br>All           | <b>2</b>                                  |
| <b>Air Quality</b>                                                                                                 | Exhaust Fumes<br>Dust                                                                                                                                                                                         | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures.</li> <li>2. Dampen milled surface with water cart.</li> <li>3. Use water cart where required.</li> </ol>                                                                                                                | Supervisor<br>All           | <b>3</b>                                  |
| <b>Bitumen/Prime</b>                                                                                               | During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.                                                                                                       | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Plan prime or bitumen operation so that it is conducted during fine weather.</li> <li>2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly.</li> <li>3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.</li> </ol> | Supervisor<br>All           | <b>2</b>                                  |
| <b>Community Relations</b>                                                                                         | Inconvenience as a result of works/traffic management                                                                                                                                                         | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken.</li> <li>2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.</li> </ol>                                            | Supervisor<br>All           | <b>3</b>                                  |
| <b>Flora &amp; Fauna</b>                                                                                           | Some works may require the removal of vegetation. Native fauna may be at risk from excavation works                                                                                                           | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage.</li> <li>2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.</li> </ol>                                                                              | Supervisor<br>All           | <b>3</b>                                  |
| <b>Heritage &amp; Archaeology</b>                                                                                  | Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist.</li> <li>2. Develop a project specific procedure based on the findings and recommendations.</li> <li>3. Installation of exclusion fencing and signage if required.</li> </ol> | Supervisor<br>All           | <b>2</b>                                  |

| Work Activity Risk                                          | Hazard                                                                                                                                                                                                                                                                                                                 | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Responsible Person/s | Risk Class after Controls in place |
|-------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
| <b>Noise Pollution, Community Relations &amp; Vibration</b> | Sensitivity to noise - to public & fauna                                                                                                                                                                                                                                                                               | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Work undertaken during “normal” hours where possible.</li> <li>2. Affected residents notified in person or in writing.</li> <li>3. Plant and equipment regularly serviced &amp; fitted with efficient mufflers.</li> <li>4. Magnitude of vibration reduced by using smaller plant etc.</li> </ol>                                                                                                                                                                                                                                                                                     | Supervisor<br>All    | <b>2</b>                           |
| <b>Soil Management &amp; Water Quality</b>                  | Soil needs to be managed to ensure that; there are no off-site impacts.<br>Damage to stockpile areas (not prepared properly).<br>Mud deposited onto roadways.                                                                                                                                                          | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Wash down machinery in only nominated areas.</li> <li>2. Not within 20 metres of water courses.</li> <li>3. Use only approved and nominated stockpile areas.</li> <li>4. Build bund wall out of material available on site.</li> <li>5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.</li> </ol>                                                                                                                                                                                                                    | Supervisor<br>All    | <b>3</b>                           |
| <b>Fuels and Chemicals</b>                                  | Contamination of waterways due to spillages of oil, degreasers, diesel, etc.                                                                                                                                                                                                                                           | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Store fuel and chemicals in accordance with relevant standards/guidelines.</li> <li>2. Minimise storage on site and locate storage facilities away from drains and waterways.</li> <li>3. All containers to be clearly labelled and Safety Data Sheets are available on site.</li> <li>4. All drums stored securely and in a bunded area.</li> <li>5. Spill kits or alternative spill containment materials available on site.</li> <li>6. Regular maintenance of plant hoses.</li> <li>7. Use correct refueling equipment.</li> </ol>                                                | Supervisor<br>All    | <b>2</b>                           |
| <b>Visual Impact Litter and Amenities Waste Management</b>  | Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive.<br>Production generated lighting, litter, mud, dirt and dust may also impact residents. | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents.</li> <li>2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately.</li> <li>3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site.</li> <li>4. Broken-out paved surfaces shall be repaired as soon as possible.</li> <li>5. Remove all rubbish from site each day.</li> <li>6. Waste asphalt will be recycled where possible.</li> </ol> | Supervisor<br>All    | <b>3</b>                           |

|                                                                                         |                |                                      |                          |            |                                      |                                 |
|-----------------------------------------------------------------------------------------|----------------|--------------------------------------|--------------------------|------------|--------------------------------------|---------------------------------|
| <b>Personal Protective Equipment</b>                                                    |                |                                      |                          |            |                                      |                                 |
| All site personnel must wear the required PPE specified in the controls above, such as: |                |                                      |                          |            |                                      |                                 |
| Safety Hi-vis<br>Vests/Shirts                                                           | Safety Boots   | Sunscreen                            | Broad Brimmed<br>Sun Hat | Sunglasses | Gloves specific to the task          | White reflective overalls/night |
| Hard Hat where<br>required                                                              | Safety Glasses | Hearing protection<br>where required | Long clothing            | Dust masks | Respiratory equipment if<br>required |                                 |

|                                                                                                                                    |                                                                                                                                        |                                                                                                                     |                                                                                                 |  |
|------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|--|
| <b>Workers may require Task Specific Training depending on activity each worker will be required to fulfill.</b>                   |                                                                                                                                        |                                                                                                                     |                                                                                                 |  |
| <ul style="list-style-type: none"> <li>All workers shall hold a current Construction Induction Card</li> </ul>                     |                                                                                                                                        |                                                                                                                     |                                                                                                 |  |
| <ul style="list-style-type: none"> <li>If required Client Site Induction</li> <li>Activity Induction (SWMS &amp; SWP's)</li> </ul> | <ul style="list-style-type: none"> <li>Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)</li> </ul> | <ul style="list-style-type: none"> <li>Plant Operators licences or competency assessments where required</li> </ul> | <ul style="list-style-type: none"> <li>Competencies for Work Zone Traffic Management</li> </ul> |  |
| <ul style="list-style-type: none"> <li>First Aid certificate training</li> </ul>                                                   | <ul style="list-style-type: none"> <li>Manual Handling training</li> </ul>                                                             | <ul style="list-style-type: none"> <li>Fire Extinguisher training</li> </ul>                                        | <ul style="list-style-type: none"> <li>Fatigue Management Training</li> </ul>                   |  |

|                                                                                                              |  |  |  |
|--------------------------------------------------------------------------------------------------------------|--|--|--|
| <b>A Site Specific Induction &amp; Toolbox Meeting will be held each day prior to the start of each job.</b> |  |  |  |
|--------------------------------------------------------------------------------------------------------------|--|--|--|

|                                                                                                                                            |                                      |                                                       |                                                      |
|--------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------|-------------------------------------------------------|------------------------------------------------------|
| <b>Legislation &amp; Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)</b> |                                      |                                                       |                                                      |
| Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022                                                                    |                                      |                                                       |                                                      |
| <b>Codes of Practice</b>                                                                                                                   |                                      |                                                       |                                                      |
| Confined Spaces - 2020                                                                                                                     | Hazardous Manual Tasks - 2020        | Managing Noise & Preventing Hearing Loss at Work-2020 | Managing Risks of Plant in the Workplace - 2018      |
| Construction Work - 2020                                                                                                                   | How to Manage WH&S Risks - 2018      | Managing Risk of Falls at Workplaces - 2020           | Managing Electrical Risks in the Workplace -2019     |
| Excavation Work - 2020                                                                                                                     | First Aid in the Workplace - 2018    | Managing Work Environment & Facilities - 2020         | WHS Consultation Co-operation & Co-ordination - 2018 |
| Welding Processes - 2021                                                                                                                   | How to Safely Remove Asbestos - 2020 | Managing Risk of Hazardous Chemicals - 2018           | Safe Design of Structures - 2018                     |

|                                                                                                                                                                                                                                                                                                                                                                                                                        |  |  |  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|
| <b>Plant &amp; Equipment for this activity</b>                                                                                                                                                                                                                                                                                                                                                                         |  |  |  |
| <ul style="list-style-type: none"> <li>All plant is inspected prior to sending out to site</li> <li>Daily maintenance &amp; service checks.</li> <li>Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out.</li> <li>Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.</li> </ul> |  |  |  |

|                                                                                                            |  |  |  |
|------------------------------------------------------------------------------------------------------------|--|--|--|
| <b>List of plant for this Activity</b>                                                                     |  |  |  |
|                                                                                                            |  |  |  |
| <b>Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):</b> |  |  |  |
|                                                                                                            |  |  |  |

**Implementation, Monitoring and Review of SWMS**

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

**SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS**

| Name (please print clearly) | Signature | Company | Date |
|-----------------------------|-----------|---------|------|
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.