


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	REMOVAL OF PITS THAT DO / DO NOT CONTAIN ASBESTOS AND REPLACE	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	 Signature
			<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L Likely	M Moderate	U Unlikely
H (1) (High level of harm)	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) (High)	1	1	2
M (2) (Medium level of harm)	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) (Medium)	1	2	3
L (3) (Low level of harm)	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) (Low)	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Prior to start of works that may involve removal of product that may contain non-friable asbestos.	To prevent injuries or illness to workers.	1	1. An asbestos licence holder must ensure that the asbestos removal supervisor appointed to supervise the removal of non-friable asbestos containing material is readily accessible to the persons performing the asbestos removal work at all times when the work is being performed.	Manager	2
Training	To prevent injuries or illness to workers	1	1. All persons engaged in the removal of material that may contain asbestos are to be trained in the hazardous of asbestos and informed, instructed and trained to perform work in a manner that is safe and without risk to health.	All	2
1. Parking of vehicles and control of pedestrians & traffic. Set out work area.	Struck by passing vehicles or public.	1	1. Implement Traffic & Pedestrian Management Plan as applicable including 'Workman Ahead' signs where required. 2. Barricade area off or sign appropriately to restrict access by public including any confined space area. 3. All workers to wear safety vests. 4. Plan movement of materials. 5. Ensure vehicles are parked legally. 6. Ensure vehicle flashing lights are operating.	Supervisor All	2
2. Pre-start site safety inspection and tool box meeting	Various hazards may include slips, trips, falls.	1	1. Prior to the start of works the supervisor will conduct a site safety inspection and address all workers about the hazards of the site and job process at a toolbox meeting. 2. Toolbox meeting to include the work process and correct PPE to be worn when dealing with possible asbestos containing material. 3. Minimum PPE to include suitable disposable clothing if required, steel toe capped work boots, hi-vis vests or clothing where required, suitable gloves and disposable respirators as required.	Supervisor All	2
3. Wet down pits to prevent escape of possible airborne asbestos fibres.	Possible inhalation of asbestos fibres	3	1. Pits are wet down prior to removal to protect the health of workers.	All	3
4. Remove pit by hand with no fragments or dust to be created.	Multiple skeletal disorders – sprains & strains.	2	1. Lever out in pieces with crowbar or shovel where already broken or cracked. 2. Use two/three man team lifts where appropriate.	All	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
			3. Use correct manual handling techniques - Lifting and lowering to be done in a smooth motion.		
	Hand injuries	3	1. Use suitable gloves and dispose of at end of with waste material.	Workers	3
	Cuts, abrasions from hand tools	2	1. Ensure tools are inspected prior to use and are in good order.	Workers	3
5. Removal of waste	Hazardous waste (asbestos) to land fill	1	1. Segregate hazardous waste. 2. Asbestos containing waste product to be placed in suitable plastic bags and labelled where applicable. 3. If the waste is not contained in sealed bags, it must be wetted before it is transported. 4. Asbestos containing waste to be taken to an approved waste facility such as Wollert or Laverton	Workers	2
6. Decontamination	Possible inhalation of asbestos fibres	1	1. All tools used to perform removal of possible contaminated material shall be washed after use. 2. Disposable clothing shall be disposed of with asbestos waste.	All	2
7. Replace pit	Multiple skeletal disorders – sprains & strains.	2	1. Lever out in pieces with crowbar or shovel where already broken or cracked. 2. Use two/three man team lifts where appropriate. 3. Use correct manual handling techniques - Lifting and lowering to be done in a smooth motion.	All	3
Additional safety issues	Sunburn may cause skin damage.	1	1. Workers to wear long pants, long sleeves, sun hats, sunscreen as per 'Personal protective equipment' procedure.	All	2
	Heat Stress	2	1. Management assess the environment during the day and put in place heat stress management techniques such as; ensuring workers drink sufficient cool water, take regular breaks & shade covers provided where practicable.	Supervisor	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Bitumen/Prime	During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.	1	1. Plan prime or bitumen operation so that it is conducted during fine weather. 2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly. 3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.	Supervisor All	2
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste asphalt will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.				
All workers shall hold a current Construction Induction Card				
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training	

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.			
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)			
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022			
Codes of Practice			
Confined Spaces - 2018	Hazardous Manual Tasks - 2018	Managing Noise & Preventing Hearing Loss at Work-2018	Managing Risks of Plant in the Workplace - 2018
Construction Work - 2018	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2018	Managing Electrical Risks in the Workplace -2018
Excavation Work - 2018	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2018	WHS Consultation Co-operation & Co-ordination - 2018
Welding Processes - 2018	How to Safely Remove Asbestos - 2018	Managing Risk of Hazardous Chemicals - 2018	Safe Design of Structures - 2018

Plant & Equipment for this activity	
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.	

List of plant for this Activity	
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):	

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.