


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	MONTHLY & ANNUAL FIRE HYDRANT TESTING	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Signature: 			
Approval to use this SWMS: “I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use”			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	<u>31/08/2025 – V12.0</u> Date
		 Signature	

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

SWMS Title: MONTHLY & ANNUAL FIRE HYDRANT TESTING				SWMS NO. 067	Page 2 of 4
Person responsible for ensuring compliance with this SWMS:	Scott Crerar	Contact Number: 1300 287 669		Date: 15/01/2020	Revision: 1.0
Project / Client: TasWater			Location: TBA		
Work Method / Task Description	Hazard Identification	Risk Level	Recommended Actions / Controls for Prevention	Residual Risk	Person Responsible
1. Arrive at site, set up pedestrian and traffic controls, complete SSRA/JSEA – select SWMS 67. Ensure any prevalent risks arising from hazards are mitigated to ALARP (AS LOW AS REASONABLY PRACTICABLE) NOTE: If you are using a Vacuum Truck with this process ensure SWMS 54 & 57 are adhered to in full.	Site specific	3	Conduct Paneltec JSEA/SSRA – conduct Tailgate Meeting	3	Sup./Worker
	issues Worker	3	Check test equipment and PPE are all on hand and adorned	3	Worker
	safety	3	Clear area and use appropriate barricades and signage.	3	Worker
	Public access and unauthorised Persons		Place appropriate traffic signs in area if and where required.		
	Stray Electrical Discharges	1	Check Hydrant Cover and underlying fitting with volt stick (do not proceed if red light emanates) contact TasNetworks immediately.	3	Sup/Worker
	Potential Sharps (CBD Area)	1	Examination of Hydrant – Using Needle Stick Proof Gloves and Torch.	3	Sup/Worker
			Use of sharps kit and tongs if necessary, to dispose of needle.		
2 Conduct an environmental check on the water discharge path. Log into TasWater testing application. Conduct inspection of equipment in accordance with TasWater’s Application and the Australian Standard AS1851 Part 4.	Slip, Trip or Fall where hydrants are located near stair landings or footpath/curb edge.	3	Cordon off any potential slips trips or falls with traffic cones. Confirm correct PPE equipment is on (hard hat, safety glasses, highly visible long sleeve shirt and long cotton pants, cut factor 4 gloves, steel cap boots).	3	Worker
	Stormwater Contamination from silted/blocked up gutters	2	Use of sedimentary silt bags if water discharge path is dirty or likely to contaminate stormwater system. Vacuum truck at hand for cleaning and jetting purposes if and where required	3	
		3	Ensure “Construction Worker” warning signage and/or traffic signs are all in place and test fitting outlet is facing the stormwater drain Apply correct manual handling protocols and follow the testing procedure as specified in the application/standard.	3	

3. Presence of Water Check discharging water.	Slip, Trip or Fall when hydrant has been discharged for presence of water check and water has dripped onto road/footpath	3	Traffic cones with tiger striped extendable bars to alert the public passing by the site should be in place around the anticipated water discharge area. Discharge minimum amount of water into bucket or if practicable into a water drain. Use	3	Worker
---	--	---	--	---	--------

Work Method Statement Title :	MONTHLY & ANNUAL FIRE HYDRANT TESTING			SWMS NO. 067	Page 3 of 4
Work Method / Task Description	Hazard Identification	Risk Level	Recommended Actions / Controls for Prevention	Residual Risk	Person Responsible
4. During service and on completion ensure all hand tools are placed back into service pouch and remove any rubbish caused by service. Record results of service on Certificate of Inspection (COI) before moving to the next piece of equipment.	Slip, Trip or Fall.	3	Tidy up work area at regular intervals and keep area free of tools on ground, minimise a tripping hazard.	3	Worker
5. Upon completion and/or at the end of test complete Taswater application and save it.	NIL	NIL	NA	NA	Worker
Additional items identified on site					

SWMS Title: MONTHLY & ANNUAL FIRE HYDRANT TESTING				SWMS NO. 067		Page 4 of 4	
Personnel Qualifications and Experience Required		Personnel Duties and Responsibilities			Training Required to Complete Work		
Technicians trained and competent in the testing of Fire Hydrants		Technician to carry out daily inspections of work site for hazards. All personnel to maintain tidy work area on site at all times. Personal Protective Equipment (PPE) to be worn at all times on site. Technician to ensure equipment and power supplies have been inspected tested and tagged. All personnel to carry and maintain a First Aid Kit. Stop work rather than accept a safety risk. On the job skills training to be conducted by Supervisor to personnel.			Person to be trained in testing of Fire Hydrants Technician to be trained in risk identification, assessment and control eg, JSEA/SSRA. Technician to be appropriately trained, qualified and competent in OH&S and electrical practices for the task.		
Engineering Details / Certificates / WorkCover Approvals / Australian Standards				Referenced – AS1851 - 2012			
Testing to be completed in accordance with AS 1851 Part 4:		<u>Tasmania:</u> Workplace Health and Safety Act 2012, Workplace Health and Safety Regulations 2012, Electricity Industry Safety and Administration Act 1997 , Electrical Industry Safety and Administration Regulations 1999					
Plant / Equipment Required (Mobile or Static)		Maintenance Checks / Calibration Intervals		PPE to be utilised as required			
				Hard Hat, Ear protection (where necessary), Eye protection, Safety Vest, Long pants/long sleeves, Cut Factor 4 Gloves			
Read, Understood & Signed by all Persons involved		1.		2.			
3.		4.		5.			
6.		7.		8.			

WORK ACTIVITY BRIEFING**Implementation, Monitoring and Review of SWMS**

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.