

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman: _____	Date:	
High Risk Construction Work:	TEMPORARY TRAFFIC MANAGEMENT	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Signature: _____			
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
John Guy	Director - Paneltec Pty Ltd	0408 449 023	31/08/2026 – V12.0
Name	Position	Signature	Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L Likely	M Moderate	U Unlikely
H (1) (High level of harm)	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) (High)	1	1	2
M (2) (Medium level of harm)	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) (Medium)	1	2	3
L (3) (Low level of harm)	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) (Low)	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Prior to leaving depot	Lack of experience	1	1. All workers must be company inducted prior to commencement. 2. New workers will be assigned a mentor through the training phase. 3. All persons will hold a construction induction card 4. All Traffic Controllers to be accredited in accordance with DOS- Traffic Control for Work on Roads-2020 guidance notes, AGTTM and AS1742.3	Management	2
	Insufficient, inadequate or unserviceable equipment for task	1	1. Conduct a pre-start on plant before commencing shift. 2. Ensure equipment is clean, serviceable and loaded onto vehicle, and there is sufficient equipment to comply with Traffic Guidance Scheme.	Traffic Controllers Team	2
	No first aid kit, fire extinguisher or emergency items out of date	2	1. Ensure emergency equipment is not out of date and in vehicle.	Team	3
Arriving on site: Tailgate Meeting & Site-Specific Risk Assessment (SSRA)	No designated parking area- risk of being struck by traffic	1	1. Identify safe parking areas, exit vehicle from no traffic side or when there is a break from approaching traffic and it is safe to do so. 2. Adorn PPE in accordance with the Australian Standards, AS/NZS 4602.1:2011 (high-visibility safety garments) and AS/NZS 1906.4:2010 (retroreflective materials). 3. Conduct Tailgate Meeting with crew and customer 4. Decide on your radio channel, share it with the customer. 5. Complete your SSRA for the site on Lucidity and detail any changes that need to be made to the SWMS in the space provided. Designate/photo TGS.	Traffic Controllers	2

Traffic Guidance Schemes (TGS)- (Set up Drawing) Traffic Management Plan (TMP)- (Written set up plan)	No prestart prior to job starting - Personal Injury	1	1. Traffic Controllers to verify that the correct signage, control devices Traffic Management Plan (TMP) and Traffic Guidance Scheme (TGS) are onsite and ready for implementation. 2. Verify all traffic controllers have PPE in accordance with the Australian Standards, AS/NZS 4602.1:2011 (high-visibility safety garments) and AS/NZS 1906.4:2010 (retroreflective materials). 3. Traffic Controller to adopt whichever control measure(s) is applicable to the site/situation as per TGS and or TMP: • Establish/Verify the clear escape route for all traffic controllers. • All control measures, traffic control devices and signage as per the TGS • Sequence of setup to be in accordance with TGS installation sequence. 4. If additional guidance to the TMP is required - refer to the Department of State Growth (DSG) <i>Traffic Control for Work on Roads-2020 Guidance Notes</i> and <i>Austroads Guides to Temporary Traffic Management (AGTTM)</i> and AS1742.3 5. If changes to the TGS are required due to operational conditions, changes may be made by a senior traffic controller providing they are documented. 6. Due diligence must be applied when setting up traffic control as personnel are working unprotected, except for the traffic vehicle with flashing arrow board and flashing lights on. 7. Refer to the TMP and TGS for all additional site-specific set up procedures. 8. Barricade the work area, to prevent inadvertent access by public. 9. Ensure all pedestrians and cyclists have safe passage around the work site. 10. Traffic control set out vehicles to display flashing amber lights & flashing arrow board. Reverse beepers and vehicle horn must all be functional. • Safety signage and traffic control devices will conform with the <i>DOS-Traffic Control for Work on Roads-2020 guidance notes</i>, <i>AGTTM</i> and <i>AS1742.3</i> to ensure safety and minimise inconvenience to traffic.	Supervisor Traffic Controllers Team	2
---	--	-----------------	---	--	-----------------

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Fit for Work	Traffic Controller presenting on site under influence of drugs/alcohol.	1	- Stand down worker immediately. - Call Manager who will conduct drug/alcohol testing. - Worker not to return to site until a non-negative test has been produced and medical clearance obtained.	Supervisor	2
Setting Out or taking down Roadwork Signage for Traffic Control	Being struck by oncoming traffic or construction plant	1	- Controller to adopt whichever control measure(s) is applicable to the site/situation: - Establish escape route - Truck mounted attenuator present if available. - Refer to the <i>Austroads Guide to Temporary Traffic Management</i>, the Tasmanian Department of State Growth-Transport Traffic Control for Work on Roads-2020 guidance notes and or Viatec's Traffic Guidance Scheme or the site-specific, Traffic Management Plan as to form of traffic management that is needed for the site eg signs, cones etc. Great care must be taken when setting up traffic control as personnel are working unprotected, except for the sign vehicle with flashing lights activated. - When available, it is preferred that two operators set up traffic control and the following rules be observed. - Do not attempt to cross the road without looking both ways first. - Communicate with each other and always warn of approaching traffic. - Always walk, do not run. - Traffic control vehicles when setting out, utilise mounted arrow boards, flashing amberlights, reversing beepers and horn. - For Line Marking & Line Removal the work area may be barricaded off with witch's hats to restrict access and minimise plant working area if practicable. - Safety signage and traffic control procedures will conform with the Department of State Growth-Transport Traffic Control for Work on Roads-2020 guidance notes and <i>Austroads Guide to Temporary Traffic Management</i> to ensure safety and minimise inconvenience to traffic.	Traffic Controllers Team	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
			11. Give advance warning where needed Traffic control devices and signs provide advance warning signs at an appropriate distance from the work areas, to ensure that approaching drivers can see the cones and or signs, in plenty of time to be able to pass through your work site slowly and safely. 12. Delineate the works clearly - Traffic must be clearly shown the path through the works using hazard markers, cones or similar devices. 13. Place signs where they will do their job properly. Refer to the above noted guidance publications and Viatec setup plans. The signs shall: - be placed at least 1 metre clear of traffic paths wherever possible. - Be mounted securely. - Be placed in the driver's line of sight. - Not be obscured by parked cars, trees, etc. - Not obscure the drivers view of other signs or other traffic. - Not be a hazard to workers, pedestrians or other road users. 14. Provide safe and convenient paths for pedestrians. - Paths shall be safe, as convenient as possible and at least 1.2 metres wide. 15. Do not interfere unnecessarily with traffic flow. - If the roadway needs to be closed, if possible, avoid peak hours or other times when traffic would have to start queuing. 16. Ensure that workers are wearing approved safety clothing (i.e. reflective high visibility vests) to increase worker visibility to passing traffic. 17. Don't leave unattended traffic signs and devices out at night unless they are designed 'after-care' setups. The signs, devices and layouts may not be suitable for night time use. Ensure the works are protected by webbing or barricades if necessary. 18. Remove the signs and cones at the finish of the work. Remove all devices and signs as soon as they are no longer needed.		

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Removal or covering of traffic control devices causing confusion for passing motorists	1	1. Remove or cover traffic control devices in correct sequence and conduct a drive-through when all controls are removed or covered.	Traffic Controllers Team	2
	Supervisor/Client unaware that worksite has been dismantled.	1	1. Ensure Supervisor/Client has been personally advised before leaving job site.	Traffic Controllers Team Leader	2
Control of Traffic Movements	Being hit by traffic	1	1. During mobile operations- controller must remain in vehicle at all times. 2. When a static site the controller must - Establish an escape route. - Remain vigilant - Follow established Traffic Controller Approved Procedure.	Traffic Controllers Team	2
	Equipment/Vehicle failure	1	1. If a TC vehicle is damaged or unserviceable, notify supervisor immediately to arrange repair or replacement vehicle.	Traffic Controllers Team Leader	2
	Traffic control devices removed, stolen, relocated or knocked over.	1	1. Regular checks to be completed and devices replaced and/or weighted as required.	Traffic Controllers Team Leader	2
	Increase in traffic speed and flow	1	1. Monitor increase in traffic speed and flow and discuss with Supervisor.	Traffic Controllers	2
	Fog, weather and lighting conditions worsen, or workplace conditions change	1	1. Discuss with Supervisor taking into consideration all safety aspects and any course of action that is required to ensure the workplace remains safe at all times. 2. If fog conditions are providing less than 200 metres clear visibility of approaching traffic, stop works immediately. 3. In Lightning conditions, do not use hand held baton – acts as conductor	Traffic Controllers	2
Other hazards	Manual Handling tasks may cause sprains, strains, back injury & fatigue.	2	1. Manual handling risk assessments are completed by Manager and workers are trained in control measures such as lifting techniques. 2. Traffic Controllers are to request assistance when they deem an item too heavy to be lifted by one person. 3. Take regular breaks from manual handling tasks.	Manager Traffic Controller Supervisor	3
	Sunburn may cause skin damage.	1	1. Traffic Controllers are to wear long pants, long sleeves, and all PPE in accordance with Paneltec's PIPE policy	Traffic Controllers	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Heat Stress	2	1. Management to assess the environment during the day and put in place heat stress management techniques such as ensuring workers drink sufficient cool water, take regular breaks & shade covers provided where practicable.	Supervisor	3
	Worker fatigue	1	1. Monitor fatigue levels through assessments, discussions with co-workers. 2. Worker is responsible for notifying Supervisor immediately if they are feeling fatigued or unwell. 3. Take breaks as per Department of State Growth-Transport Traffic Control for Work on Roads-2020 guidance notes.	Supervisor Traffic Controllers	2
	Distraction from use of mobile phones	1	1. DO NOT USE MOBILE PHONES when actively controlling traffic as per approved procedures except in the case of an extreme emergency.	Traffic Controllers	2
	Worksite changes reducing safety of workers	1	1. Discuss with Supervisor and team and adjust site as required. Changes to a TGS are to be noted in the diary or SSRA.	Traffic Controllers	2
	Traffic controller leaving site	1	1. No traffic controller is permitted to leave site until a replacement has been brought to site to relieve you. 2. Notify your Supervisor immediately to discuss your requirements.	Traffic Controllers	2
Working at night or in poor visibility	Run over by vehicular traffic.	1	1. Traffic Controllers to wear high visibility vests and or garments as specified for night works. 2. Temporary lighting is to be used to light work areas. 3. Retroreflective warning signs used. 4. Illuminated wands may be used to guide vehicular traffic and reversing vehicles at night. (In Lightning conditions do not use baton – acts as conductor).	Traffic Controller Supervisor	2
Identifying additional daily hazards	Various	Vary 1 to 3	1. Prior to the start of a particular project, the Supervisor and Traffic Controllers Team Leader will walk the work site (or remotely review) and identify any additional potential hazards. The management of these hazards will be discussed and documented below.	Supervisor	2-3
Records		3	1. Records must be kept of all traffic control plans, signs, audits, incidents etc- refer to Department of State Growth-Transport Traffic Control for Work on Roads-2020 guidance notes.	Supervisor	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers are available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits are on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has a prolonged adverse effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Drivers to check vehicle tyres/bodies for buildup of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled, and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refueling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat (Events Only)	Safety Glasses	Gloves specific to the task	White reflective overalls/night
Hard Hat with sun brim	Ear Plugs (if required)		Long clothing	Dust masks (if applicable)	Respiratory equipment (if required)	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.				
All workers shall hold a current Construction Induction Card				
- If required Client Site Induction - Activity Induction (SWMS & SSRA's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training	

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.

Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)			
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022			
Codes of Practice Guides & Standards			
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020	Managing Risks of Plant in the Workplace - 2018
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020	Managing Electrical Risks in the Workplace -2019
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020	WHS Consultation Co-operation & Co-ordination - 2018
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018	Safe Design of Structures - 2018
Austroroads – Guide to TTM Parts 1-10	AS/NZS 1742.3 2019 - MUTCD Part 3	Department of State Growth-Transport Traffic Control for Work on Roads-2020 guidance notes.	Traffic Training Course Notes

Plant & Equipment for this activity
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.

List of plant for this Activity
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):

PANELTEC PTY LTD
P O Box 148 Kings Meadows, TAS 7249
ABN: 12 128 689 412
WORK ACTIVITY BRIEFING

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.