


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	REFUELLING OF PLANT ON SITE	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
John Guy Name	Director - Paneltec Pty Ltd Position	0408 449 023 	 Signature
			31/08/2025 – V12.0 Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

<u>Level 1</u> Eliminate the hazard
<u>Level 2</u> Substitute the hazard with something safer.
<u>Level 3</u> Isolate the hazard from people. Reduce the risks through engineering controls.
<u>Level 4</u> Reduce exposure to the hazard using administrative actions.
<u>Level 5</u> Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training and skill	Un-trained persons could cause injury to themselves and others. Possible property damage.	1	1. All persons on site must carry with them a current 'Construction Induction Card'. 2. All persons working on site must be suitably licensed, trained and competent in the work they are to perform. 3. No person shall operate mobile plant or equipment without the appropriate licence or where no licence is available without an appropriate training competency assessment certificate in the safe use of the particular piece of plant or equipment they are to operate, and they have read and understood the specific plant or equipment operation manual. 4. All persons on site shall have read and understood and signed off on this SWMS & Site Specific Induction.	Management	2
Emergency Situation	Fire Accident/Incident	1	1. Stop what you are doing immediately. 2. Assess the situation. 3. Use the fire extinguisher if safe to do so, and you have been trained in its safe use. 4. Advise your Foreman – he will call emergency services and initiate the emergency procedures. 5. First Aid person to initiate first aid if safe to do so.	All	2
Personal Protective Clothing & Equipment (PPE)	Personal injury. Moving plant/equipment Sun/Heat Slips/trips Noise with levels above 85dBA Wet weather Dust Vapours	1	1. Minimum PPE to be worn on site is: • Hi visibility vests/clothing. • Steel toe-capped boots (lace up). • UV skin protection minimum 15+ UV sunscreen & insect repellent. • Head protection as applicable eg wide brimmed sun/hard hat. • Long pants and long sleeves. • Safety glasses or sunglasses. • Hearing protection as required. • Face and hand protection as required. 2. Seat belt to be worn whilst equipment is in use.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Preparation – Refilling fuel cart/tank at service station	Fire / explosion	1	1. No smoking is permitted at any time during refueling activities. 2. No mobile phone usage while refueling. 3. Tested and tagged fire extinguishers appropriate for the task, to be available on truck with identifying signage for quick & easy access. 4. Operator to have completed firefighting awareness training. 5. Follow service station safety procedures (signs/directions).	All	2
	Mechanical failure – injury from moving plant	1	1. Truck/plant initially start work at a site and are inspected prior to using. 2. Daily pre-start inspections are conducted on all plant and trucks by the operators. 3. Regular checks/service on roll over fuel cut-off valve. 4. When stationary ensure the truck is in park (gear) and “blocking chocks” are applied to the wheels on the down side of slop.	All	2
	Uncontrolled Spills	1	1. Ensure Safety Data Sheet is available on site for specific fuel. 2. Ensure a spill kit is available on site.	All	2
Arrival on site and prepare for re-fuelling operations (Re-fuelling Location)	Plant movements	1	3. Notify site staff of impending arrival. 4. Activate hazard lights, rotating warning lights, reverse alarms and reversing camera when entering and exiting the site. 5. Plant (machines) to be located in a designated fuelling area e.g. Bunding/spill kit area, away from pedestrian movement. 6. Check location of fire extinguishers and spill kits in the vehicles and on site.	Operator	2
	Slips, trips and falls	2	1. Use 3 points of contact rule when climbing on/off back of the truck or when entering or exiting the truck cabin. 2. Wear appropriate footwear with sufficient ankle support. 3. Be aware of uneven / slippery surfaces prior to exiting from vehicle.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Re-fuelling operations: For small plant items e.g. generators and approved fuel containers	Re-fuelling containers from back of ute/truck Fire/explosion, static-ignition	1	1. A risk assessment should be conducted for the control of static-electricity. 2. PPE to be worn – Flame resistant clothing and hydrocarbon proof long sleeves / pants, steel capped boots, eye protection, goggles, long gloves. 3. Re-fuelling operations and Plant (machines) to be located in a designated fuelling area e.g. Bunding/spill kit area, away from pedestrian movement and where practical, operations should take place in an open and well ventilated area away from buildings structures and shelters. 4. Remove approved fuel containers off the back of the ute/truck. Place on a flat and level ground/earth before re-fuelling. Use a funnel if required. 5. Only use fit for purpose fuel containers that meet the requirements of AS/NZS 2906 – FUEL CONTAINERS and AS/NZS 1940 – STORAGE and HANDLING. 6. Before re-fuelling small plant items allow enough time for the cooling down of engine and exhaust (“auto ignition” may occur with “petrol” at temperatures of 280 – 456 Degrees Celsius, refer to SDS). Use a funnel to eliminate spills while refuelling containers and small plant items e.g. generators. 7. Check location of fire extinguishers and spill kits in the vehicles and on site.	Operator	2
Re-fuelling operations: For machine plant	Manual handling injury	2	1. Training in manual handling. Follow correct manual handling procedure, reduce repetitive movement, wear appropriate footwear, and use mechanical aids where possible, warm up exercises when practical.	Operator	3
	Vehicle and plant fuel spills, fire/explosion	1	1. Plant (machines) to be located in a designated fuelling area e.g. Bunding/spill kit area, away from pedestrian movement. 2. Check location of fire extinguishers and spill kits in the vehicles and on site.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Slips, Trips and falls	2	1. Use steps and handrails provided, three point of contact at all times while getting on/off back of fuel tank and exiting, or entering trucks / plant. 2. Ensure access path is clear of obstacles. 3. Beware of wet slippery slopes / surfaces. 4. Wear appropriate footwear. 5. Fuel hose to be kept at minimal distance at all times while re-fuelling.	Operator	3
	Fuel spills (fire)	1	1. Spill kits to be on truck and topped up after use. 2. PPE to be worn, long sleeves / pants, safety helmets, steel capped boots, high visibility clothing for night and day work, eye protection, glasses / goggles, long PVC gloves. 3. Training in manual handling. Follow correct manual handling procedure, reduce repetitive movement, and use mechanical aids where possible, warm up exercises when practical. 4. Re-fuelling operations to be undertaken at the location identified as a suitable site designated by Supervisor.	Operator	2
	Injury from vehicle and plant movement	1	1. Follow on site Traffic Control Plan and traffic controller's instructions. 2. Check revision mirrors and reversing monitor before reversing. 3. When stationary ensure the truck is in park (gear) and "blocking chocks" are applied to the wheels on the down side of slop. 4. All staff and contractors to maintain 3 metres clearance from plant and equipment in operation, and/or within the area of influence of revolving plant items (hose reels and lines).	Operator	2
	Poor lighting	3	1. Activate hazard lights, rotating warning lights and vehicle lights. 2. Engage spot light. 3. PPE to be worn, safety helmets, steel capped boots, high visibility clothing for night and day work, eye protection, glasses / goggles, long PVC gloves. 4. Day makers to be installed at site (designated fuelling area) as required.	Operator	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Pack up equipment and exit site.	Traffic movements	1	1. Ensure flashing orange warning lights and hazard lights are operational. 2. Pack up signs and cones and ensure that hose connections and fuel operation systems have been shut down. Check hoses and connections are secured in the back of the vehicle. (No loose items). 3. PPE to be worn high visibility vests, safety helmets (if required), steel capped boots.	Operator	2
	Manual handling injury	2	1. Follow correct manual handling procedure, reduce repetitive movement, wear appropriate footwear, use mechanical aids (gripper tool) where possible, team lift, warm up exercises when practical.	Operator	3
	Slips, Trips and falls	2	1. Use three point of contact at all times while entering/exiting vehicle. 2. Use of steps and handrails provided (entering/exiting trucks & plant). 3. Ensure access path is clear of obstacles.	Operator	3
	Fast approaching traffic while merging	1	1. Wait for appropriate gap in traffic. 2. Enter traffic at same speed; switch off flashing lights and hazard lights once merged. 3. Obey road rules and (VMP).	Operator	2

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Bitumen/Prime	During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.	1	1. Plan prime or bitumen operation so that it is conducted during fine weather. 2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly. 3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.	Supervisor All	2
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during “normal” hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste asphalt will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

WORK ACTIVITY BRIEFING

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.