

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	SITE ESTABLISHMENT - Customer Access Network (CAN) NBN Co. Network	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025 SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> Phone	<u>31/08/2025 – V12.0</u> Date
		 Signature	

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L Likely	M Moderate	U Unlikely
H (1) (High level of harm)	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) (High)	1	1	2
M (2) (Medium level of harm)	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) (Medium)	1	2	3
L (3) (Low level of harm)	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) (Low)	2	3	3
Level Likelihood / Probability					
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
1.0	Job Prestart					
1.1	Contracted Construction Resource – Paneltec (CCR) receives a Job Pack from Console.	Unidentified hazards, personal Injury Where access to a premises is required contact the customer prior to attending the site to assist in identifying local hazards i.e. Dogs and other domestic animals	1	1. CCRs are to contact the customer on the nominated contact point prior to proceeding to the site. 2. Mobile phones are not to be used whilst driving. 3. CCRs are to ask the owner to secure dogs or other domestic animals before attendance. 4. CCRs are to ask the customer or contact person of their knowledge of any site specific hazards, including the presence of asbestos. 5. For Customers Not in Attendance (CNIA) access and conduct testing at the side of the house if a Lucca / Madison box / or external Main Distribution Frame (MDF) is accessible. 6. If no external test point is present or one that requires opening a gate the CCR is to access the joint outside the customers' premises (CP).	CCR	2
1.2	Soil Assessment – All Ground Breaking Activities	Environmental Contamination Prosecution from Regulator	1	1. Telstra will conduct a desktop assessment for Preliminary Soil Screening (PSS) for all ground breaking activities. 2. Soil will be classified into: • Class 1 (Likely contaminated soils are present); • Class 2 (Unlikely contaminated soils are present, but surrounding land uses are identified as potential sources of contamination); or • Class 3 soil (Inert soil - uncontaminated) 3. Soil classification will be located under 'Project View' on ground breaking activity Work Orders.	Telstra	2
1.3	Notify Neighbours – 30 days prior to work commencing	Risk to members of the public and workers from exposure to Asbestos related diseases	1	1. Contractor to letter drop to residents where any soil breaking activity is to be completed thirty (30) days before work is to be undertaken. Minimum timeframe 48 hours. • Residences/business adjacent to where asbestos work is to be undertaken. • Residences/business two doors up from where asbestos work is to be undertaken. • Residences/businesses on opposite side of road from where asbestos work is to be undertaken. 2. Resident notifications should also be extended, at the subcontractor's discretion, to include high	CCR	2

				traffic/pedestrian/visibility areas such as nearby Childcare Centres and Grocery Stores 3. Rural/Remote areas - the letter can be posted, however it must still comply to these requirements. 4. Emergency Works – there is no need to provide 30 days’ notice to residents for emergency work, however, contractors must contact residents in the immediate vicinity of any ground breaking activity the ACM works prior to commencing the works. 5. Letters are to be delivered in a sealed Telstra branded envelope.		
2.0	Travel to and from work site					
2.1	Travel to and from work site	Driver incompetence	1	1. Driver to have current driver’s license 2. Driver to adhere to all road rules 3. Driver not to use mobile phone unless connected to ‘hands free’ unit.	CCR / Driver	2
		Vehicle Roadworthy Serious injury or death	1	1. Vehicle registered 2. Compulsory insurance cover maintained on vehicle (i.e. comprehensive insurance and Third Party Car Insurance) 3. Regular maintenance undertaken on vehicle 4. Vehicle is in a roadworthy condition 5. Safety defects are to be rectified before undertaking work with ISGM.	CCR / TM	2
		Adverse conditions or Telstra’s identified Black, Red, Amber or Green Zone	1	1. Adverse conditions – Black, Red, Amber, and Green Zones communicated to CCR by text from Telstra. 2. CCRs are not to proceed to areas identified as a Black zone. 3. Applies to critical infrastructure and network only. CCR’s are permitted to enter Red zones after approval from Telstra State ELSO or Telstra State Deputy ELSO. 4. CCRs to assess if it is safe for them to proceed to an Amber zone and notify their TM if they are to do so. 5. CCRs can access Green zones if no additional hazard exists.	CCR / TM / all workers	2
		Hazardous locations – Telstra, Temporary Hazardous Locations (THLs), and Special Work Locations (SWLs)	1	1. CCRs are to assess that their work location is not listed in Telstra’s THL or SWL listing. 2. If listed CCRs are to contact their TM for assistance.	CCR / TM / all workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Use of Laptop, Phone or GPS Navigation unit whilst driving	Personal Injury Vehicle damage	1	- CCR to use mobile phones, GPS navigation units and laptops only when the vehicle is stopped and parked legally. - Hands free kits to be installed in vehicles where phone is used	CCR / TM / Driver	2
	Motor vehicle malfunction	Personal Injury Vehicle damage	1	- Vehicles to maintained and serviced to manufactures specifications. - Driver to ensure vehicle inspections are performed e.g. lights, indicator, lights, brake lights, tyre pressure and vision.	CCR / TM / Driver	2
	Unsecured loads from roof racks, trailer and inside vehicle	Personal Injury Vehicle damage	1	- Ensure roof racks have been secured and installed properly to the roof of the vehicle. - Ensure all equipment is properly secured to roof racks prior to driving. - Tie down straps, ropes, chains inspected for defects before use. - Vehicle to have cargo barrier installed where required and all items stored securely before travel.	CCR / TM / Driver	2
	Fatigue	Increased risk of vehicle accidents due to extended travel times	1	- Use and follow Stop. Revive. Survive model. Rest 15 minutes every two hours - Where practical, ensure power naps are taken. - CCRs instructed to advise their Team Manager (TM) of issues that may adversely affect their ability to operate a vehicle/complete works. - Drive to Heavy Vehicle Log book	CCR / TM / Driver / all Workers	2
	Vehicle hitting animals (especially in rural areas)	Personal Injury Vehicle damage Wildlife and animal endangerment	1	- Drivers to exercise extreme caution when travelling in rural areas and watch out for native and wild animals and livestock. - Driver to take note of native animals and livestock warning signs. - Drivers to take extreme caution when driving at night to avoided striking native animals and livestock. Extra caution is to be taken during dawn and dusk driving.	CCR / TM / Driver / all Workers	2
	Road rage	Personal Injury Vehicle damage	1	- Driver is to adhere to road rules and drive in a safe manner. - Driver is not to drive aggressively or in a threatening manner, i.e. speed, tail-gate, cut off other drivers (especially semi-trailers). - Driver is not to provoke aggressive or threatening behavior to other drivers. - If deemed necessary, lock vehicle doors whilst driving.	CCR / TM / Driver / all Workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Illegal or Unsuitable Parking	Fire Vehicle damage Serious personal injury	1	1. CCRs are to park their vehicles according to road rules of their State or Territory. 2. CCRs are to park on hard surfaces ensuring the vehicle doesn't become bogged. 3. Vehicles that may become bogged from time to time are to seek assistance from a licensed vehicle retrieval service at their cost. 4. CCRs are to avoid parking on long grassy areas due to the increased risk of fire from hot components under the vehicle. 5. For safe unloading of tools and equipment the placement of Witches Hats at the rear of the vehicle reducing the chance of other motorists restricting the ability to unload or load tools or materials. 6. Park to the Traffic Control Plan set up by an approved Traffic Control company.	CCR / Drivers	2
	Isolation	Personal Injury	1	1. For CCRs traveling to isolated areas they are to follow ISGMs Working in Isolation requirement with ability to contact emergency services confirmed by CCR supervisor.	CCR / TM	2
3.0	Loading and Unloading Plant and Equipment					
3.1	Prior to Departure	Personal Injury Equipment Damage Prosecution	1	1. Perform a risk assessment to assess site and transport risks 2. Competent operators to move plant of and on trucks and trailers 3. Ensure equipment is ready for transport: e.g. no loose fittings, fleet inspection completed 4. Ensure truck has capacity for plant/equipment 5. Heavy equipment to be loaded by mechanical aids, e.g. Hiab. Ramps etc. 6. Only equipment that has been rated to lift equipment or materials shall do so. The Safe Working Load (SWL) is to be affixed to the lifting equipment. 7. Lifting chains and slings are to be used by trained personnel. 8. Lifting chains and slings to be inspected prior to use. 9. Cranes / hoists are to be operated by trained personnel. 10. Ensure firm, level ground where possible when loading 11. Establish clear No-Go Zones around plant/equipment loading area 12. Use a Spotter to guide loading as required	CCR / Operator / Spotter/ Driver	2

				13. Plant/equipment driver (where required) to wear seatbelt when moving piece of plant/equipment 14. Apply appropriate tie down chains, straps for transport 15. Driver is to verify plant/equipment is tied down appropriately 16. Driver to check vehicle and contents height to ensure safe transport (i.e. low bridges)		
3.2	Arrival at Site	Personal Injury Equipment Damage Manual handling injuries	1	1. Perform a risk assessment to assess the unloading area site risks. 2. Ensure firm, level ground is available for unloading 3. Competent operators to move plant of and on trucks and trailers 4. All mobile plant to be appropriately registered. 5. Remove all tie down chains, straps etc. 6. Heavy equipment to be unloaded by mechanical aids, e.g. Hiab. Ramps etc. 7. Clear No-Go (unloading) Zones before unloading 8. Unloading trucks should not be done by a plant operator of a forklift or crane unless the operator can see the truck driver is well clear of a designated exclusion zone. 9. Only equipment that has been rated to lift equipment or materials shall do so. The Safe Working Load (SWL) is to be affixed to the lifting equipment 10. Use a Spotter to guide unloading and movement of mobile plant/equipment through worksite as required	CCR / Operator/ Driver / Spotter / Workers	2
3.3	Use of Spotter	Slip, trip fall hazard Personal Injury from plant or equipment	1	1. Spotters to wear appropriate PPE i.e. high visibility clothing, safety boots, hard hat (if required) 2. Ensure the designated unloading area is clearly defined, hazards minimised and spotter and plant operator 3. Agree communication method with the Spotter before unloading begins 4. Do not commence un loading until the Spotter is ready and gives the signal to do so 5. Ensure everyone is a safe distance from the transporter vehicle and mobile plant operator remains in visual contact with the spotter. If not STOP until visual contact is restored. 6. Mobile plant operator and other workers are to follow directions from the Spotter.	CCR / Operator / Spotter/Worke rs	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
3.4	Operation of Plant/Equipment	Personal Injury from plant or equipment	1	1. Plant operators to be licensed or have letter of competency (State/Territory regulations apply) 2. Unloading trucks should not be done by a plant operator of a forklift or crane unless the operator can see the truck driver is well clear of a designated exclusion zone. 3. Spotter should always be in the sight of the plant operator 4. High visibility clothing to be worn by plant operator and spotter. 5. Exclusion zone to be implemented near mobile plant.	CCR / Plant Operator / Spotter / Workers	2
		Manual Handling injuries	1	1. Ergonomic team lifting where required and where mechanical aids cannot be used. 2. Where ramps are deployed manually, two person lift is required.	CCT/ competent operator / all workers	2
		Hit by falling plant	1	1. All personnel are to stay away from suspended loads and reversing plant. 2. Hat hats to be worn by workers when near lifted loads	CCT/ competent operator / all workers	2
4.0	Site establishment and de-establishment					
4.1	Site establishment and de-establishment	Inadequate Induction, unidentified hazards, personal injury	1	1. All workers to have Construction Induction card issued by State/Territory Regulator. 2. All workers to be inducted on worksite. 3. All workers to be involved in the completion of site/project Job Safety Environmental Analysis (JSEA). 4. All workers to be aware of Safe Work Method Statements (SWMS) for the activities they are to perform at the worksite. Workers are to sign SWMS as evidence that they have read and understand the contents of the SWMS. 5. All visitors to be inducted on worksite and sign the JSEA as evidence that they understand the risks associated with the worksite. 6. A 'vehicle pack' containing safety information, policies and procedures, safety register, emergency contact lists etc. are to be maintained at worksite whilst any worker remains at the worksite.	CCT / TM / Supervisor/all workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
		Aggressive customers or members of the public	1	- CCR to contact the customer or site contact and assess the customers' needs and identify potential threats posed by the customer. - For immediate threats the TM / CCR are to exit to a safe place and to call 000 and request the police. - The CCR is to notify their TM of the incident immediately. - If the customer or other members of the public threatens the CCR or uses language that may indicate a potential threat, the CCR is to remove themselves away from the dangerous situation and then to contact their Team Manager (TM) for guidance / assistance. - CCR is not to enter customer's premises unless an adult is in attendance.	CCT / TM / Supervisor /all workers	2
		Being hit by other vehicles or plant	1	- Ensure you park in safe and legal position. - Use hazard lights, dome rotating flashing lights and cones as appropriate. - Check all mirrors before stepping out of the vehicle. - Care taken when unloading equipment from vehicle. - Setup Traffic/Pedestrian management as required. - Use Traffic Control Devices and signage when working on roadway. - Refer to Traffic Control document.	CCT / TM / Supervisor /all workers	2
		Working on premises without permission	2	- Permission to be obtained from client and customer (resident) prior to entering site. - Client site inductions to be attended by all relevant workers prior commencement of works if required. - All workers and visitors inducted to worksite, if applicable.	CCT / TM / Supervisor /all workers	3
		Unsafe practices in construction / work sites	1	- PPE (including but not limited to hardhat, safety boots and fluorescent high visibility garments) to be worn at all times when on site. - Construction Induction Card to be carried on site at all times. - Take care when working near mobile plant and ensure that operator is aware of your presence. - Ensure you are inducted to the Clients Site Safety induction prior to commencing work on their sites.	CCT / TM / all workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
		First aid awareness and emergency- Working in Isolation	1	1. Ensure that vehicle is equipped with an up to date first aid kit. (Refer relative State/Territory WHS Regulations or Code of Practice). 2. Copy of emergency phone numbers is to be located in vehicle. 3. Working in isolation is to be avoided if possible. If required implement a contact protocol with your Team Manager (TM). 4. Always let somebody know where you're going and how long you will be. 5. Carry mobile phone with you when you are away from the vehicle and regularly check for reception. Ensure mobile phone has an adequately charged battery. 6. Ensure you have extra survival items when working in isolation, especially food, water and warm clothing. 7. Call emergency services on 000 (or 112 for mobiles) in the event of any emergency.	All workers	2
		Insect and Pests - Spider, insect or snake bites	1	1. Assess the area for potential insect or pest hazards. 2. Snakes and spiders are never to be caught, harassed or interfered with. 3. Be aware of snakes and spiders under debris or when lifting manhole/pit lids. 4. Consider insect repellent. 5. Check for Ticks after the completion of work in tick infested areas. 6. Always wear safety boots, and use gloves when performing this activity. 7. For insect or pest infestation such as bee hives etc. contact your TM who will notify Telstra of the Hazard and will recommend a Temporary Hazardous Location (THL) to be recorded. CCRs are to return the Ticket of Work (TOW) to Telstra if they are unable to transpose and complete the task.	CCR / TM / all workers	2
		Needle stick injuries	1	1. Use gloves and plastic/metal tools to collect syringes/needles or other sharp implements. 2. Dispose of needle in approved container (sharps container). 3. Use gloves and plastic/metal tools to clean pits, do not use bare hands. Dispose of sharps at an authorised location (i.e. doctors' surgery, hospital, authorised sharps disposal site).	All workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
		Incorrect manual handling of heavy items	1	- Workers trained in manual handling techniques - Items that are too heavy for a two man lift are to be moved / lifted by mechanical means. - Job rotation & regular rest breaks	CCR / all workers	2
		Slips, trips, falls and barbed wire	2	- Do not jump or climb over fences, unless it is absolutely necessary to do so. - If it is necessary to climb over barbed wire, place a blanket or other strong material on top of wire, prior to climbing over. Wear leather gloves and long trousers. - When walking through long grass be aware of trenches, uneven ground, holes or steep and slippery surfaces; - Wear appropriate PPE, i.e. steel capped boots, leather gloves and long trousers.	All workers	3
		Weather conditions – heat, cold or rain	1	- Use correct PPE and approved appropriate clothing depending on weather conditions. - Implement appropriate health measures i.e. take regular breaks, adequate fluid intake, work in shade during extreme temperatures and rotate workers. - Wear adequate wet weather gear, if required. - Observe all fire bans. - Identify emergency evacuation point. - UV sunblock is to be kept onsite and worn as appropriate.	CCR / TM / Operator / all workers	2
		UV radiation - sunburn, sunstroke or dehydration	1	- Locators to wear protective clothing, including broad brimmed hat, sunglasses, long pants and shirts when applicable. - Use sunscreen according to directions. Reapply every two hours. - Drink plenty of water to stay hydrated. - Take regular breaks in the shade.	CCR / TM / All workers	2
		Extreme weather (i.e. Storms / Lightning)	1	- Re-schedule work if possible. - Take cover during storms (do not seek protection under trees). - Don't use conductive tools during thunder storms. - Wear High Visibility clothing.	CCR / TM / All workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
5.0	Site Hazard Identification					
5.1	Complete site hazard identification	Failure to adequately identify site hazards	1	1. Prior to commencing work, CCR in conjunction with all site workers will undertake a visual hazard identification of the site. 2. In conjunction with 1 above a JSEA will be completed each day which will identify any hazard identified during the visual inspection. 3. All hazards identified will have appropriate controls put into place prior to any work commencing. 4. Discuss all hazards and controls with workers and any visitors to site. 5. JSEA is to be signed by all workers and visitors to show they have been made aware of the site hazards and what controls are in place to minimize those hazards.	CCR / TM / All workers	2
		Striking/damaging overhead services/Electrical Contact	1	1. Undertake a visual inspection of the work site to identify if the plant may contact overhead services. If the plant apparatus comes within: • Less than 3.0m of overhead electrical asset no work is to proceed - refer requirements detailed in WHS-17 Work Near Overhead Electrical Wires Procedure Electrical Spotters - No Go Zones • 3.0m to 6.4m of overhead electrical asset a competent spotter is required. • Where the works to be undertaken are more than 6.4m from the electrical assets work may proceed provided the equipment is monitored to ensure it does not breach the above requirements.	CCR / TM / All workers	2
6.0	Working in Direct Sunlight and/or Extreme Hot Weather					
6.1	Working in direct sunlight and/or extreme hot weather	Dehydration	1	1. Provide cool clean drinking water in close proximity to work area. 2. Take regular drink breaks. 3. Rest in shaded area.	CCR / TM / Supervisor & all workers	2
		UV Exposure	1	1. Refer to daily newspapers/radio for sun smart UV alert rating. 2. Download and use Sun Smart app for iPhones and Androids. 3. Where possible schedule works out of direct sunlight. 4. Ensure appropriate consultation has been carried out prior to the work commencing. 5. Carry out appropriate risk assessment. 6. All personnel to be supplied with personal protective equipment	CCR / TM / Supervisor /all workers	2

				adequate for providing UV protection. • Shirts with collar and long sleeves. • Trousers or knee length shorts. • Sunglasses – UV rated. • Hard hats with brim extension or broad brimmed floppy hat. e. Sunscreen – minimum 30+ UV.		
		Heat Stress	1	1. Implement agreed rest breaks i.e. 10 minutes per hour, task rotation. 2. Encourage workers to drink water not soft drinks. 3. Work in/under shade if possible. 4. If possible don't work in direct sunlight between 10:00 am and 3:00 pm.	CCR / TM / Supervisor /all workers	2
6.2	Treatment for Heat Cramps Heat Exhaustion Heat Stroke	Symptoms: • Poor concentration, • Prickly heat • Muscle cramps • Headache • Fatigue • Nausea • Lack of co-ordination • Confusion • Irritability	1	1. Seek medical assistance immediately 2. Trained first aid officer to be on site. 3. Where a person is affected by heat stress remove to coolest place with shade covering, where there is circulating air and have person lie down. 4. Fan person down. 5. While waiting for the medical assistance sponge person with cold water and give sips of cool water to drink if conscious. 6. Do not administer soft drinks.	CCR / TM / Supervisor /all workers	2
7.0	Working in Extreme Heat/Cold					
7.1	Site establishment	• Dehydration • UV Exposure • Heat Stress • Heat Craps • Heat Exhaustion • Heat Stroke • Cold Stress	1	1. Prior to work review local weather conditions to determine if additional precautions are required. 2. Complete JSEA prior to work. Environments and work locations where there is a potential for heat or cold stress will be identified, risk assessed and documented 3. First aid officer to be on site. 4. Check temperature at regular intervals throughout day and stop work if too hot 5. During summer or on extreme hot days, re-organise work schedule so that work is performed in the cooler parts of the day 6. Rotate employees between hot and cooler working conditions 7. Organise regular rest periods.	CCR / TM / Supervisor /all workers	2

				8. Reduce physical demands by using mechanical assistance or job rotations to those that are less physically demanding 9. Ensure adequate supply of cool drinking water is available and that workers are regularly replenishing their fluids. 10. Ensure warm drinks and conditions for cold temperatures 11. Use respirator with built in drink bottle facility (Bottle Drinking to suit full face M98 RESP 012598) 12. Allow for short breaks where PPE can be removed to avoid heat related discomfort. When undertaking asbestos removal work this will require asbestos PPE to be decontaminated, removed and disposed of as per Asbestos (ACM) SWMS. When work resumes a new set of asbestos PPE is to be worn. 13. Provide shade covering (portable gazebo) if possible to reduce radiant heat from the sun 14. Wear appropriate clothing that still provides adequate protection against the elements, sun, cold, wind. 15. Wear tinted safety glasses with UV protection 16. 30+ Sunscreen to be supplied and applied 30 minutes before work outdoors and commences and regularly throughout the day		
Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
8.1	Access to Telstra Pit / Manholes Outside of Customer's Premises	Pits and Manholes – personal injury	1	1. CCRs are to implement the appropriate SWMS for accessing specific Telstra Pits and Manholes. 2. Refer ISGM-HSE-PAA-SWMS-0114 Manhole-Pit Work. 3. CCR's are not to enter confined spaces without the appropriate accreditations, entry permits, staff and equipment.	CCR / TM / All Workers	2
		Broken Telstra pits and manholes- slip trip fall and manual handling injuries	2	1. ISGM TMs to undertake Telstra e-Learn <i>Make Safe Pits and Manholes</i>. 2. CCRs to install a footway board above damaged broken pits and manholes before leaving the site. 3. CCRs to install a large footway board only with assistance from a second CCR for manual handling. 4. CCRs to install a complete set of guards in an A frame secured to the pit or manhole if a footway board cannot be installed. 5. CCRs to contact their TM for replacement guards. If no replacement guards are available and the CCRs guards are depleted CCRs are not to work in the external plant until replacement guards are obtained.	CCR / TM / All Workers	3

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
9.0	Traffic and Pedestrian Management					
9.1	Traffic and Pedestrian Management	Setting up traffic / pedestrian signs	1	- Only Accredited Traffic Management Personnel to Set Up Equipment (unless directly supervised) by accredited person. - Traffic / Pedestrian signs to be setup in accordance with traffic management plan and are able to manage all pedestrians and traffic to ensure a safe working environment. - Traffic plans scenario to be recorded on the JSEA. - Wear high visibility clothing. - Ensure pedestrians are detoured safely around work area using; fencing, barricades, cones, or safety tape. - Site is to be adequately sign posted.	CCR / TM / All Workers	2
		Hazard to workers due to road traffic on roadway whilst setting up worksite safety measures	1	- Activate rotating dome flashing lights and hazard lights on CCR vehicles. - All workers to wear high visibility clothing. - Additional Traffic Controller to Use Stop / Slow Bat to warn motorists if possible. - Accredited traffic controller card required. - Erect signage at lead taper first & work towards work zone.	CCR / TM / All Workers	2
		Traffic Control Devices and Signage not set up correctly	1	- Only Accredited Traffic Management Personnel to Set Up Equipment (unless directly supervised) by accredited person. - Refer to Traffic Management Plans	CCR / TM / All Workers	2
		Risk of Falling from heights	1	- Be aware of your surroundings and identify height hazards. - Wear safety harness as required. - Care to be taken when climbing onto vehicles and when unloading and loading plant, equipment or materials off trucks and vehicles.	CCR / TM / All Workers	2
		Manual Handling	2	- Apply ergonomic principles when establishing worksite. - All Workers to have completed manual handling training. - Two man lifts or use mechanical aids (i.e. lifting arm, hiab, crane).	CCR / TM / All Workers	3
		Unqualified Staff	1	- Only certified and competent personal to use equipment / vehicles/ or plant. - Copies of licenses or certificate/letter of competency are to be held on site. - Trainees to complete log book under the guidance/direction of a competent trainer.	CCR / TM / All Workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
		Unauthorized Access	1	1. Traffic management plan to be developed and adhered to. 2. Secure work site to allow access to authorized personnel only. 3. Visitors to be inducted to site.	CCR / TM / All Workers	2
10.0	Installation and removal of barricades and signs					
10.1	Perform risk assessment on area to be barricaded.	Slips, trips, falls	2	1. Site hazards to be identified on JSEA. 2. Be cautious when walking through long grass for sunken trenches, uneven ground, holes or steep and slippery surfaces. 3. Wear appropriate PPE, i.e. steel capped boots, long trousers. 4. Ensure safe pedestrian access is available when establishing site.	CCR / TM / All Workers	3
10.2	Erect barricade	Incorrect manual handling of heavy items	2	1. Apply ergonomic principles when establishing worksite. 2. All workers to have completed manual handling training. 3. Items that are too heavy for a two man lift are to be moved or lifted by mechanical means. 4. Implement job rotation and regular rest breaks practices.	CCR / TM / All Workers	3
		Being hit by other vehicles or plant	1	1. Traffic / Pedestrian signs to be setup in accordance with traffic management plan and are able to manage all pedestrians and traffic to ensure a safe working environment. 2. Traffic plans scenario to be recorded on the JSEA. 3. Wear high visibility clothing. 4. Ensure pedestrians are detoured safely around work area using either: barricades, cones, or safety tape. Site is to be adequately sign posted.	CCR / TM / All Workers	2
		Weather conditions – heat, cold or rain	1	1. Use correct PPE and approved appropriate clothing depending on weather conditions. 2. Implement appropriate health measures i.e. take regular breaks, adequate fluid intake, work in shade during extreme temperatures and rotate workers. 3. Wear adequate wet weather gear, if required. 4. Observe all fire bans. 5. Identify emergency evacuation point. 6. UV sunblock is to be kept onsite and worn as appropriate.	CCR / TM / All Workers	2
		Barricade Construction	1	1. Barricades are erected for the purpose of: • providing a visual barrier; • restricting worksite access to unauthorized persons;	CCR / TM / All Workers	2

				• protect persons from falling into manholes and pits; • containment of plant, equipment and materials; and • preventing interaction with an identified hazard. 2. Barricades shall be installed in such manner that will not expose the public to any additional hazard while providing a safe path where pedestrians can safely pass without being exposed to increased risk. 3. Depending upon the work being undertaken barricades can consist of: • Temporary fencing • Guards • Cones • Safety tape • Star pickets and mesh type fencing 4. Refer section 7.4 <i>Star Picket Barricades - Installation</i> for installation requirements of star pickets.		
10.3	Disassemble barricades	Incorrect manual handling of heavy items	2	1. Apply ergonomic principles when establishing worksite. 2. All Workers to have completed manual handling training. 3. Items that are too heavy for a two man lift are to be moved or lifted by mechanical means. 4. Implement job rotation and regular rest breaks practices. 5. Refer section 7.5 <i>Star Picket Barricades – Dismantling</i> for dismantling requirements for star pickets.	CCR / TM / All Workers	3
		Being hit by vehicles or plant	1	1. Traffic / Pedestrian signs are setup in accordance with traffic management plan and are able to manage all pedestrians and traffic to ensure a safe working environment. 2. Wear high visibility clothing. 3. Ensure pedestrians are detoured safely around work area until barricades removed. 4. Do not remove signs until after barricade dismantled.	CCR / TM / All Workers	2
		Weather conditions – heat, cold or rain	1	1. Use correct PPE and approved appropriate clothing depending on weather conditions. 2. Implement appropriate health measures i.e. take regular breaks, adequate fluid intake, work in shade during extreme temperatures and rotate workers. 3. Wear adequate wet weather gear, if required. 4. UV sunblock is to be kept onsite and worn as appropriate.	CCR / TM / All Workers	2

10.4	Star Picket Barricades - Installation	Body injuries, abrasions and hitting underground services – Explosion or electric shock	1	5. Take care with wet equipment (i.e. barricades) as it could be slippery. 1. Clear any obstacles in the way of where the temporary barrier is to be installed. 2. Check DBYD to ensure no underground services are located where the star picket barrier is to be installed. (Refer next Task for appropriate actions.) 3. Never use bent star pickets as a component of any barricade. 4. Mark ground where pickets to be installed at maximum spacing of 3 metres apart. 5. Place star picket rammer/driver over star picket and ram picket into ground. 6. Picket should be driven at least 600mm into the ground. 7. Fit safety caps onto star picket. 8. Secure caps to top of picket to ensure they are not removed inadvertently e.g. cable ties, duct tape. 9. Secure mesh barrier or tape to star pickets e.g. cable ties. 10. Where mesh barrier is used it is to be overlapped by at least 150mm and secured to prevent unauthorised persons from entering the protected area.	CCR / TM / All Workers	2
		Hitting underground services with star pickets	1	1. Before erecting star pickets the following precautions are to be implemented to ensure there are NO underground services that will be damaged by star picket. 2. Confirm location of all underground assets in the work area against the relevant Dial Before You Dig (DBYD) documents. 3. Ensure all DBYD drawings are current and up to date. 4. The location, path and approximate depth of underground assets or services are to be identified using a calibrated electronic cable locator and/or potholing. 5. Ensure all services have been clearly marked on ground with the depth and what service it is e.g. • Yellow gas • White communications • Red power • Blue water 6. Use paint to mark locations on ground. 7. If underground services located do not install star picket above service.	CCR / TM / operator spotter / Supervisor	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
10.5	Star Picket Barricades - Dismantling	Manual handling injuries Cuts and abrasions	2	1. Salvage any material that can be used for future use. 2. Remove mesh barrier from star pickets. 3. Use star picket extractor (Post Lifter) puller to remove the star picket. 4. Do not wriggle the star picket out of the ground as they will bend. 5. Fill any hole left in the ground following removal of star picket as it could pose a trip hazard. 6. Clean up all materials including off cuts cable ties and duct tape that have been used to secure barrier material and caps. 7. Wear protective hand wear, gloves etc	CCR / TM / All Workers	3
11.0	Working In Remote Locations					
11.1	Working In Isolation	• Dehydration • UV Exposure • Heat Stress • Heat Craps • Heat Exhaustion • Heat Stroke • Cold Stress	1	1. Ample water suppliers when travelling on hot days or in remote areas. 2. Adequate communications with a TM/supervisor 3. People to know where you are 4. Ensure persons do not work alone in isolation under possible heat stress conditions. 5. If working in isolation cannot be avoided, implement a regular check-in.	CCR / TM / Supervisor /all workers	2
12.0	Night Operations					
12.1	Setting up lights for night work or areas with low lighting levels	Working at night or in low light	1	1. Night work requires the consent of local Councils through a permit system. This permit will detail conditions that will apply to the works. 2. NOTE: The exception is for undertaking emergency works, in which no permit is required. 3. Artificial lighting is to be used and set up in a suitable location(s) to illuminate the work site. 4. Traffic management plans are to reflect the impact of low light and/or night work. 5. Information about hours of work, noise levels, traffic control arrangements and lighting requirements, are to be provided to effected parties i.e. residents. 6. Reflective high visibility clothing, including pants, to be worn by all workers.	CCR / TM / all workers	2

Task #	Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
13.0	Site Clean Up					
13.1	Completion of Work, Clean Up Site	Traffic hazard - struck by oncoming traffic	1	1. Continue to wear compliant high visibility clothing. 2. Keep effective traffic and pedestrian controls in place until the site is reinstated and site is safe for pedestrians and/or vehicular traffic.	CCR / TM / all workers	2
		Slips trips and falls	1	1. Ensure pits / manhole lids are securely put back in place. 2. Pack up all tools and leads off the ground. 3. For ground breaking activities ensure ground surface is left level and will not pose future trip and fall hazards 4. Leave the site clean and tidy and safe.	CCR / TM / all workers	2
		Environmental damage	2	1. Remove socks from gutters and storm water drains. 2. Clean all soil from site. 3. Remove all rubbish from site. 4. Make good any damage to grass verges etc.	CCR / TM / all workers	3
		Manual Handling – lifting injury	2	1. Workers trained in manual handling techniques. 2. Apply ergonomic principles when reinstating workplaces. 3. Two man lifts or use mechanical aids (i.e. lifting arm, hiab, crane).	CCR / TM / all workers	3

Special Tools & equipment required:

- **Wooden Handled Crowbar**
- **Asbestos Disposal Bags**
- **Gas Detector. 4 sensor**
- **Earth mat**
- **Safety line**
- **Seal Breaker**
- **Pit key**
- **Guards**
- **Witches hats**
- **Footway boards**
- **Signage**

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task Rigger/Disposable	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.				
All workers shall hold a current Construction Induction Card				
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training	

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.			
--	--	--	--

Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)			
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022			
Codes of Practice-2018			
Confined Spaces	Hazardous Manual Tasks	Managing Noise & Preventing Hearing Loss	Managing Risks of Plant in the Workplace
Construction Work	How to Manage WH&S Risks	Managing Risk of Falls at Workplaces	How to Manage Electrical Risks in the Workplace
First Aid in the Workplace	Excavation Work	Managing Work Environment & Facilities	WHS Consultation Co-operation & Co-ordination
Welding Processes	How to Safely Remove Asbestos	Managing Risk of Hazardous Chemicals	Safe Design of Structures

Plant & Equipment for this activity	
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.	

List of plant for this Activity	
Fall arrest and retrieval system and safety ropes, Modular ladder / Step extension / Extension ladder, Telstra approved guards, Full Harness with Pole Strap, Safety Line	
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):	

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers.	Supervisor All	2
Spills to Ground	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. All containers clearly labelled and Safety Data Sheets are available on site. 3. Spill kits or alternative spill containment materials available on site.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Broken-out paved surfaces shall be repaired as soon as possible. 4. Remove all rubbish from site each day.	Supervisor All	3

WORK ACTIVITY BRIEFING**Implementation, Monitoring and Review of SWMS**

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.