


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods , plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	LIQUID WASTE COLLECTION	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: April 2026 unless required earlier		Location:	
Signature: _____ 			
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>Stephen Guy</u> Name	<u>Manager - Paneltec Pty Ltd</u> Position	<u>0408 176 442</u> 	 Signature
			<u>23/04/2025 - V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

<u>Level 1</u> Eliminate the hazard
<u>Level 2</u> Substitute the hazard with something safer.
<u>Level 3</u> Isolate the hazard from people. Reduce the risks through engineering controls.
<u>Level 4</u> Reduce exposure to the hazard using administrative actions.
<u>Level 5</u> Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
			load, duly completed waste data forms about the consigned waste, and must provide a copy of each to the waste facility or mobile waste processor to which the load is delivered. 4. No person should drive or operate vehicles or equipment unless they are licensed and have been competently trained to do so. 5. No person shall operate plant or equipment under the influence of alcohol, illicit drugs or prescription drugs that affect their ability to work safely. 6. Workers to wear correct safety footwear and PPE at all times, including safety vest/clothing. 7. Vehicles to be equipped flashing beacon lights, hazard lights and reversing beepers.		
Pre-start checks Truck	Unsafe working conditions Increased likelihood of incident during operation.	1	1. Vehicle used to transport waste must be kept in a clean condition and be constructed and maintained so as to prevent spillage of waste. 2. Conduct a pre-start safety check of vehicle as per 'Operator Pre-Start Checklist' prior to the start of work. 3. Clean windows. 4. Maintain trucks in clean, highly visible condition with particular attention to brakes, rear number plate & lights. 5. Ensure required PPE is available in the vehicle – Extra vest, gloves, glasses, hats, sunscreen, first aid kit, fire extinguisher, spill kit & safety triangle.	Management Workers	2
Starting checks	Unsafe working conditions Increased likelihood of incident during operation	1	1. The operator must be seated and in full control of the vehicle when starting. 2. Test steering, limiting devices and all equipment controls. 3. Listen and watch for defects. 4. Test brakes, hand brake. 5. Test lights, horn and backup alarm.	Workers	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Personal Hygiene Considerations	Serious illness even death	1	Toxic materials may be inadvertently ingested or absorbed through the skin due to improper personal hygiene practices. To minimize the possibility of this occurring: 1. Do not eat, drink or smoke in the work area. 2. Always wash hands (minimum) and face before eating, drinking or smoking. 3. Wear protective coveralls over street clothes or specially laundered industrial garments in work areas and remove these before leaving. Garments heavily soiled or soaked with hydrocarbon should not be worn but should be exchanged or discarded for clean garments. 4. Shower thoroughly after completion of work. 5. Avoid handling foam ear hearing protectors with unwashed hands. 6. Immunizations such as tetanus must be kept up to date. Basic primary series of 3 doses - Booster every 10 years and Hepatitis injections.	Workers	2
Proceed to Collection designated area	Unsafe working conditions, increased likelihood of incident during operation if controls not followed	1	1. At all times drive safely, obey all road laws and consider the safety of all road users. 2. No unauthorized person is to ride in the cabin of the vehicle. 3. Driver and crew members to use 3 points of contact when getting in and out of vehicle. 4. High visibility vests/clothing are to be worn at all times.	Workers	2
Prior to Entering site	Potential injury from movement of vehicles or equipment on site if site rules are not known. Possible injury from not using appropriate tools and equipment or safety PPE.	1	1. Site Induction and Supervised Work Access Pass if required (site authorization). 2. Ensure appropriate tools and safety equipment and PPE are available in vehicle for use as required e.g. high visibility vest/clothing safety helmet, full length clothing, safety boots etc	Workers	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Driving around site.	Potential injury from movement of vehicles or equipment on site if site rules are not known.	1	- Follow rules of site. - Flashing lights, reverse beepers and flags (if required).	Supervisor	2
Site hazard assessment	Potential injury to all workers & bystanders if site hazards are not discussed and controlled.	1	Complete a site hazard assessment, implement control measures & hold a toolbox meeting with all workers who will be involved in the works.	Supervisor	2
Work Area Set Up	Pedestrian Injury	1	Set up warning signs and barricades as required to warn drivers and pedestrians of work and limit access to only authorised persons.	Workers	2
Loading of liquid waste	Various injuries to personnel and bystanders if procedures not followed	1	- Non compatible wastes must not be mixed or transported together on any vehicle used to transport waste. - Any hazardous waste or industrial waste transported must not be mixed with any other type of waste or with any other material.	Workers	2
	Manual handling hazards	2	- Take care and use the correct tool when lifting lid to sump. - Ensure hose connection is done up tight. - Be aware of hose when sucking out product as it may jump around when sucking in air. - Use legs and bend at knees when replacing lids- lower down slowly.	Workers	3
Disposing of classified liquid wastes	Environmental hazard	1	Liquids are less easily contained than non-liquid wastes, so that their dissolved and suspended contaminants have a greater potential to contaminate land and waters than non-liquid wastes. This can occur by run-off to surface waters or by infiltration through soil to sub-surface waters. If liquid waste percolates through other (non-liquid) waste at the site before run-off or infiltration, it can also be further contaminated with dissolved or suspended contaminants. For this reason, it is most desirable that liquid wastes should only be disposed of at licensed landfills.	Workers	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
General actions for dealing with spills	Environmental hazard	1	1. Stop the source of the spill immediately if it is safe to do so. 2. Contain the spill and control its flow (Refer to the relevant SDS). Stop the spill from entering any stormwater drains by blocking the drain inlets. 3. Clean up the spill. It is important to clean up all spills quickly, even small ones, as they can easily flow into stormwater drains or be washed there by rain. 4. Dispose of the absorbents used in the spill clean-up. 5. If a spill occurs that threatens or harms the environment, you must tell the EPA or the local council as soon as you can after you became aware of it. 6. For large-scale, hazardous spills call the Fire Brigade immediately on 000. If you cannot contain any spill of hazardous materials (regardless of its size) contact the Fire Brigade immediately. 7. For small-scale spills, follow the SDS for the spilled substance. 8. Make sure you are aware of emergency telephone numbers to call in the case of a spill.	Workers	2
General Safety Hazards	Bodily injuries Spills and splashes onto workers' eyes / skin	2	1. Workers always wear appropriate PPE for the task at hand eg safety boots, gloves and eye protection as a minimum.	Workers	3
	Manual Handling tasks may cause sprains, strains, back injury & fatigue.	2	1. Warm up exercises to be done prior to start of shift. 2. Appropriate manual handling techniques to be applied. 3. All workers trained in the correct lifting techniques and correct use of tools. 4. If an item appears to be too heavy or awkward ask for assistance from a crew member prior to moving the item. 5. Try not to twist your body when carrying hoses use your feet to change direction.	Workers	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
			6. Be aware of awkward areas. 7. Use a rope to control hose in sump areas.		
	Exposure to noise	2	1. Suppress noise using mufflers if required. 2. Hearing protection must be worn at appropriate times when working near noisy equipment or where equipment is suitably signed.	Management Workers	3
	Needle stick injury	1	1. Pipe blockages could be due to discarded syringes. 2. Needle collection kits to be available in each vehicle. 3. Workers to be careful not to put their hands into any liquid waste incase of discarded needles present.	Management Workers	2
	Sunburn may cause skin damage.	1	1. Workers to wear long pants, long sleeves, sun hats, sunscreen, sunglasses and lip protection as per 'Personal protective equipment' procedure.	Workers	2
	Inclement weather	3	1. Workers to wear appropriate wet weather gear.	Workers	3
	Crew members falling or tripping over on site.	3	1. Check for hidden objects/holes.	Workers	3
	Snakes	1	1. Snake bite bandages carried in first aid kit. All workers trained in correct use of bandage if bitten.	Workers	2
	Low overhead wires-electrocution	1	Operators need to keep vehicles/equipment-hoses 1. At least 3 metres from 132,000-volt lines. 2. At least 6 metres from 132,000 to 330,000-volt lines. 3. Areas closer than 3m are no go zone. 4. Use certified spotter if working near powerlines. (3m to 6.4m) 5. Clarify safe working distances with site manager. 6. If in doubt of line voltage keep at least 8 metres away.	Workers	2
	Fall injury	2	1. Workers to use 3 points of contact when climbing up and down from vehicles. 2. Ensure good footing when climbing up and down stairs to separator pits.	Workers	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled, and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refueling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste products will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.				
All workers shall hold a current Construction Induction Card				
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training	

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.			
--	--	--	--

Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)			
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2012			
Codes of Practice			
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020	Managing Risks of Plant in the Workplace - 2020
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020	Managing Electrical Risks in the Workplace -2019
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020	WHS Consultation Co-operation & Co-ordination - 2018
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018	Safe Design of Structures - 2018

Plant & Equipment for this activity			
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.			

List of plant for this Activity			

Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):			

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.