

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	VACUUM TRUCK LOADING & TYPE A WATER JETTING	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group - Operations Manager and in consultation with management and workers – 2025 SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	 Signature
			<u>28/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L Likely	M Moderate	U Unlikely
H (1) (High level of harm)	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) (High)	1	1	2
M (2) (Medium level of harm)	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) (Medium)	1	2	3
L (3) (Low level of harm)	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) (Low)	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
1. Training and skill.	Un-trained persons could cause injury to themselves and others. Possible property damage.	2	- All persons on site must carry their 'Construction Induction Card'. - All persons shall be inducted with the customer where and if necessary, a site-specific induction shall be completed (i.e. TasWater, TasGas Induction Card) - All persons working on site must be suitably licensed, trained and competent in the work they are to perform. - Type A Water Jetting Accreditation must be held by the jetting operator and the jetting operation must be <5600 BLPM All Water Jetting and any Non-Destructive Digging (NDD) operations shall be in accordance with the operating manual for the particular Vacuum Truck and the employee's training provided.	Management Operators	3
2. Personal Protective Clothing & Equipment (PPE)	Personal injury from high water pressure. Particles flicking up from ground surface. Getting wet.	2	- Minimum PPE (as per PIPE Policy) to be worn on site is: - High visibility work attire/cotton clothing - full length sleeves and pants - Safety boots/gumboots - Hard hat - UV skin protection - Hearing protection - Eye protection – Safety Glasses & or Face Shield - Rubber/Latex Gloves - Waterproof disposable coveralls	Operators	3
3. Site Specific Risk Assessment (SSRA)	Hazardous site specific and environmental parameters affecting the capacity for employees to adhere to these SWMS in a safe working manner.	2	- Chock Truck wheels if parked on an incline - Conduct Tailgate Meeting with all on-site concerned with the jetting or NDD works including Traffic Controllers - Complete Construction-Excavation SSRA within the Lucidity Platform - List any site-specific hazards that may be prevalent and introduce control measures to mitigate all inherent risk to as low a reasonably practicable. - Reference Paneltec SWMS applicable to the site in the SSRA Ensure all workers are signed onto the SSRA and submit.	Lead Operator	3

4. Set out work area.	Striking hazards with person, road or construction plant.	1	6. Cover protruding objects with a Traffic Cone to prevent running into items, remove slips trips & falls risks. 7. Check work area for additional hazards (low points, boggy areas) and note controls implemented within the Lucidity SSRA.	Supervisor All Operator	2
5. BYDA Verification	Electrocution Explosion	1	1. Review all Before You Dig Australia plans including any conditions of work issued by the relevant asset owner. 2. Verify all underground assets has been located. 3. Locate or have your supervisor arrange the location of any unidentified services. 4. Ensure Safe Operating Procedures (SOP) of the asset owner will be complied with regarding excavations. 5. Complete the Paneltec Vacuum and Mechanical Excavation permit. If the depth of the excavation is to exceed 1.5m then bench, batter or shore the excavation (or have on site, an authorised geotechnical report by an engineer of trench stability and safety). NOTE: WORKERS MUST NOT ENTER AN EXCAVATION >1.5M IN DEPTH WITHOUT THE ABOVE CONTROLS AND A PERMIT IN PLACE DETAILING ALL CONTROL MEASURES OF COLLAPSE PROTECTION. 6. If the above cannot be facilitated, do not proceed with the work, please contact your supervisor immediately.	Supervisor All	2
	Falling or tripping over on site.	2	1. Maintain good housekeeping especially hoses and electrical leads. 2. Barricade off unsafe areas. 3. Clearly mark protruding objects using paint, caps or hazard tape.	Supervisor Operator	3

6. General Safety Requirements	Personal injury to operator and other workers.	1	1. All persons who are to operate or assist with the operation of the Vacuum Truck are to be fully competent and have received information and instruction in the safe use of the machine and the potential hazards. 2. Read all instructions before using machine. 3. Know how to stop and start the vacuum and bleed pressure quickly. 4. Be familiar with controls. 5. Do not work in rain or during thunderstorms. 6. The vacuum is not to be operated by children, teenagers or persons under the influence of drugs or alcohol. 7. Operator and assistant to wear appropriate PPE – safety boots, safety glasses, long clothing, safety vests (done up to prevent entanglement) gloves, hearing protection and safety helmets where required. 8. If the vacuum is to be used with hazardous or dangerous materials- the operator must be adequately trained.	Operator	2
7. Pre start checks vacuum truck	Unsafe machine potential for injury to operator or bystanders	1	1. 1. Daily Pre start safety checks are to be completed in our lucidity software application. 2. Keep operating area clear of all persons. 3. Use a Traffic Cone next to the water jet to prevent splashes. 4. Stay alert and beware of the force of the water pressure coming out the end of the hose (around 3500psi) and when using the vacuum hose be aware of the suction pressure. 5. Do not overreach or stand on unstable supports. 6. Never aim the jet in the direction of persons or animals as the water jet comes out of the nozzle at high speed with high pressure. 7. Do not leave the operating vacuum unattended. If the vacuum is not required switch off. 8. Do not operate the vacuum in enclosed spaces. 9. Follow directions as per the operations manual.	Operator	2

8. Steps in Activity	Potential Hazards	Risk Class	10. Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
9. Operating the Vacuum Truck	Injury to operator or bystanders – high pressure- dirt and stones can be flicked around.	1	11. The pressure hose is operated with by trigger action. 12. When cleaning pipes etc the hose must first be in the pipe prior to activating the trigger.	Operator	2
	Fire hazard	1	1. Do not use near flammable liquids. 2. Turn off machine prior to refueling.	Operator	2
10. Shut down and Maintenance	Potential for personal injury	1	1. When finishing work follow end of day maintenance and shut down requirements. 2. When disassembling any part of the machine or servicing make sure the machine is turned off.	Operator	2
11. Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
12. Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. Use water cart where required.	Supervisor All	3
13. Bitumen/Prime	During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.	1	1. Plan prime or bitumen operation so that it is conducted during fine weather. 2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly. 3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.	Supervisor All	2
14. Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
15. Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
16. Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
17. Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2
18. Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
19. Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled, and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refueling equipment.	Supervisor All	2
20. Visual Impact 21. Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste asphalt will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Hearing protection	Sunglasses	Gloves specific to the task	White hooded disposable coveralls
Hard Hat	Safety Glasses	P2 Dust masks (where required)	Long clothing	P2 Dust masks (where required)	Respiratory equipment if required	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.				
All workers shall hold a current Construction Induction Card				
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training	

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.			
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)			
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022			
Codes of Practice			
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020	Managing Risks of Plant in the Workplace - 2018
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020	Managing Electrical Risks in the Workplace -2019
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020	WHS Consultation Co-operation & Co-ordination - 2018
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018	Safe Design of Structures - 2018
Plant & Equipment for this activity			
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.			
List of plant for this Activity			
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):			

WORK ACTIVITY BRIEFING

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.