

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	FLOCON TRUCK- SAFE OPERATION	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training and skill.	Un-trained persons could cause injury to themselves and others. Possible property damage.	1	1. All persons on site must carry with them a current 'Construction Induction Card'. 2. All persons working on site must be suitably licensed, trained and competent in the work they are to perform. 3. No person shall operate mobile plant without the appropriate licence or competency assessment. 4. Driver/Operator of Flocon truck must have the appropriate truck licence and have been appropriately trained in the safe operation of the vehicle.	Management	2
Personal Protective Clothing & Equipment (PPE)	Personal injury.	1	1. Minimum PPE to be worn on site is: • Hi visibility vests/clothing • Steel toe-capped boots • UV skin protection minimum 15+ UV sunscreen • Head protection as applicable • Long pants and long sleeves	All	2
Preparation for operation	Inadequate planning	1	1. Identify people, PPE, equipment, potential hazards and safety controls prior to commencement of works. 2. Supervisor to issue traffic management plan to work crew. 3. All relevant signs to be placed on vehicle. 4. Supervisor to arrange extra signs and traffic control as required. 5. SDS's for flocon operations are in vehicle for kerosene & emulsion products.	Supervisor Workers	2
Loading truck with metal & sand	Machinery	1	1. Stand clear of the loading operation and in a position where the operator can see you	All	2
Loading truck with emulsion and kerosene	Coupling not fitted correctly. Spill of materials while filling or after filling. Ignition of kerosene	1	1. Ensure that PPE is worn, including eye protection and gloves 2. Inspect coupling for wear and tear. 3. Do not over fill tank. 4. No smoking while filling kerosene.	Workers	2
Site Inspection and toolbox meeting	Various hazards	1	1. Prior to the daily toolbox meeting, the Foreman and or workers will walk the work site and identify potential hazards. 2. The management of these hazards will be discussed at the	Foreman	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
			toolbox meeting and documented on the ' <u>Site Induction/Toolbox meeting record</u> ' form.		
Traffic control	Poor Drivers Inappropriate traffic control	1	- Follow traffic management plan from Supervisor. - Ensure the traffic control measures are appropriate for all weather conditions. - Use of appropriate PPE issue high visibility clothing etc. Stay alert for traffic on worksite - Aftercare signage to be left if working on intersection and surface is loose from aggregate or stone dust.	Foreman All	2
Repair of pothole	Manual Handling Noise Vibration Traffic Hazardous substance Loose Material	1	- Practice solid lifting/bending technique when performing task. - Operator to wear hearing protection when working near noisy plant & equipment. - For vibration reduce exposure time by crew rotation. - Be aware of traffic, tourist when working on roads. - Always follow safety advice on SDS's for emulsion and kerosene. - Aftercare signage to be left if working on intersection and surface is loose from aggregate or stone dust.	Workers	2
Moving to next site	Drivers Manual Handling	1	- Workers to be aware of operating site machinery at all times.. - Collect equipment and rubbish. - Do not ride on back of truck. - Move traffic control signs to new job as per traffic management plan. - Be aware of lifting signs and frames onto vehicles.	Workers Driver	2
Use of vibrating equipment (wacker plate etc) if required	Physical Injury from Vibration.	2	- Operators to wear correct PPE; gloves, hearing protection. - Rotation of workers. - Equipment to be maintained in good working order eg. rubber grips on tools).	Operator Foreman	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Patching	Exposure to Noise levels above 85dBA for extended periods may cause Hearing damage.	2	- Noise risk assessments of all plant/equipment as per 'Hearing conservation' procedure. - Where plant/equipment is signed hearing protection must be worn by workers. - Plant/Equipment to be maintained in good working order and noise excessive equipment to be modified where practicable to reduce noise levels. - Rotation of workers.	Management All Management Foreman	3
	Manual Handling tasks such as shoveling, raking, lifting may cause sprains, strains, back injury & fatigue.	2	- Manual handling risk assessments are completed by management and workers are trained in control measures such as lifting techniques. - Workers are to request assistance when they deem an item too heavy to be lifted by one person. - Regular breaks from manual handling tasks- job rotation.	Management All Foreman	3
	Sunburn may cause skin damage.	1	Workers to wear long pants, long sleeves, sun hats, sunscreen as per 'Personal protective Equipment' procedure.	All	2
	Heat Stress	2	Management is to assess the environment during the day and put in place heat stress management techniques such as ensuring workers drink sufficient cool water, take regular breaks & shade covers provided where practicable.	Foreman	3
	Chemical/ fume exposure may cause burns or skin problems.	2	- Store and handle chemicals in accordance with Safety Data Sheets and the 'Hazardous substances and dangerous goods' procedure. - PPE provided and should be worn by workers as per SDS.	Management All	3
Identifying additional daily hazards	Could be Various	Vary 1 to 3	Prior to the daily toolbox meeting the Foreman and or workers will walk the work site and identify potential hazards. The management of these hazards will be discussed at the toolbox meeting and documented on the 'Site Induction/Toolbox meeting record' form.	Foreman	2-3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Bitumen/Prime	During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.	1	1. Plan prime or bitumen operation so that it is conducted during fine weather. 2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly. 3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.	Supervisor All	2
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during “normal” hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled, and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refueling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste will be recycled where possible.	Supervisor All	3

Personal Protective Equipment					
All site personnel must wear the following PPE specified in the controls above.					
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Sun Hat	Sunglasses	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection if required	Gloves	Face masks	Respiratory equipment if required

Training required		Plant and equipment for this activity	Plant/Equipment	Plant/Equipment
List training required (e.g. Hiab, First Aid, Traffic Control)		- All plant is inspected prior to sending out on hire - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250 hr intervals.	Flocon Truck	
☒	Construction Induction Card			
☒	Activity Induction			
☒	Site induction			
☒	Traffic Controllers Certificate	List of standard operating procedures required to operate plant /equip: Operators Handbook		
☒	Traffic Control at Worksites Cert.	Codes of Practice, Legislation	Certificates, permits, approvals etc.	
☒	Driver licences (trucks, vehicles)	List the specific Codes of Practice (COP), legislation, standards	List engineering certificates, permits, approvals etc*. required for this activity (eg road closure, utility shutdown, WorkCover notification etc)	
☒	Plant operation tickets	Work Health & Safety Act 2011 Workplace Health & Safety Regulation 2011	Type	Ref document
☒	First Aid Certificate	COP 2018 Hazardous manual tasks COP 2018 How to manage work health and safety risks	Plant & Equipment	Plant to comply with WorkCover requirements.
☒	Manual Handling	COP 2018 Managing noise and preventing hearing loss at work COP 2011 Managing the work environment and facilities	PPE	PPE to comply with Australian Standards.
☒	Use of Fire Extinguisher	Work near Overhead Powerlines COP-2018 Moving Plant on Construction Sites COP-2018 Plant Guide 2001		
		Excavation Work COP-2018 First Aid in the Workplace Guide 2018		
List of Hazardous substances that may be used or handled on site (SDS available) - Fuel-Diesel/Unleaded fuel - Bitumen				

WORK ACTIVITY BRIEFING

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.