

**SAFE WORK METHOD STATEMENT**

|                                                                                                                                                                                         |                                                       |                                                                                                          |                                          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|----------------------------------------------------------------------------------------------------------|------------------------------------------|
| <b>Persons responsible for supervising, inspecting work, work methods, plant &amp; equipment and tools</b>                                                                              | <b>Supervisor/Foreman:</b>                            | <b>Date:</b>                                                                                             |                                          |
| <b>High Risk Construction Work:</b>                                                                                                                                                     | <b>TRENCH EXCAVATION SHORING &amp; LAYING PIPES</b>   | <b>Project:</b>                                                                                          |                                          |
| SWMS prepared by Patrick Monaghan - Paneltec Group - Operations Manager and in consultation with management and workers – 2023<br>SWMS Review Date: August 2026 unless required earlier |                                                       | <b>Location:</b>                                                                                         |                                          |
| <b>Approval to use this SWMS:</b> "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"               |                                                       |                                                                                                          |                                          |
| <u>John Guy</u><br><b>Name</b>                                                                                                                                                          | <u>Director - Paneltec Pty Ltd</u><br><b>Position</b> | <u>0408 449 023</u><br> | <u>31/08/2025 – V12.0</u><br><b>Date</b> |

**RISK MATRIX**

| Level                                  | Description of Consequence or Impact                                                                                                                                                              | Consequence              | Likelihood / Probability |                      |                      |
|----------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|--------------------------|----------------------|----------------------|
|                                        |                                                                                                                                                                                                   |                          | L<br><i>Likely</i>       | M<br><i>Moderate</i> | U<br><i>Unlikely</i> |
| H (1)<br><i>(High level of harm)</i>   | Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.                    | H (1)<br><i>(High)</i>   | 1                        | 1                    | 2                    |
| M (2)<br><i>(Medium level of harm)</i> | Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.                  | M (2)<br><i>(Medium)</i> | 1                        | 2                    | 3                    |
| L (3)<br><i>(Low level of harm)</i>    | Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm. | L (3)<br><i>(Low)</i>    | 2                        | 3                    | 3                    |
| <b>Level</b>                           | <b>Likelihood / Probability</b>                                                                                                                                                                   |                          |                          |                      |                      |
| Likely                                 | Could happen frequently                                                                                                                                                                           |                          |                          |                      |                      |
| Moderate                               | Could happen occasionally                                                                                                                                                                         |                          |                          |                      |                      |
| Unlikely                               | May occur only in exceptional circumstances                                                                                                                                                       |                          |                          |                      |                      |

**HIERARCHY OF RISK CONTROL**

The hierarchy of controls must be applied in the order below for all identified hazards.

|                                                                                                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Level 1</b><br>Eliminate the hazard                                                                                                                           |
| <b>Level 2</b><br>Substitute the hazard with something safer.                                                                                                    |
| <b>Level 3</b><br>Isolate the hazard from people.<br>Reduce the risks through engineering controls.                                                              |
| <b>Level 4</b><br>Reduce exposure to the hazard using administrative actions.                                                                                    |
| <b>Level 5</b><br>Use personal protective equipment<br>The control measures that you put in place should be reviewed regularly to make sure they work as planned |

**ACTIVITY ANALYSIS**

| Steps in Activity              | Potential Hazards                                                                                              | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                | Responsible Person/s   | Risk Class After Controls In Place |
|--------------------------------|----------------------------------------------------------------------------------------------------------------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|------------------------------------|
| 1. Training                    | To prevent injuries or illness to workers                                                                      | <b>1</b>   | 1. Machinery operators will have the necessary current licence for the equipment they will operate.<br>2. All persons will have a current construction induction card.                                                                                                                                                                                              | Supervisor<br>All      | <b>2</b>                           |
| 2. Arriving on site            | Entry unsafe or unauthorised areas                                                                             | <b>1</b>   | 1. Report to site office for site induction if required.<br>2. Risk assessment of site conditions and site-specific induction & toolbox meeting to be conducted.<br>3. Consider all environmental protection issues and the impact caused by entry to site.                                                                                                         | All<br>Supervisor      | <b>2</b>                           |
| 3. Unloading Plant & equipment | Falls, slips & trips from vehicle, trucks and floats<br><br>Machinery plant tipping over or falling from ramps | <b>1</b>   | 1. Ensure all vehicles are parked in a clear level area for unloading plant and equipment.<br>2. Extra care taken in wet conditions, use a ramp to load and unload plant.<br>3. Persons unloading equipment to wear seat belt.<br>4. Operators familiar with SWMS – Loading & Unloading Plant & Equipment.<br>5. Only suitably trained personnel to work with plant | Operator               | <b>2</b>                           |
|                                | Electrocution                                                                                                  | <b>1</b>   | 1. Be aware of overhead power lines                                                                                                                                                                                                                                                                                                                                 | Operator               | <b>2</b>                           |
|                                | Traffic hazards, hit by vehicles or other on site plant and equipment                                          | <b>1</b>   | 1. Ensure hazard & warning signage is in place as required when unloading plant.<br>2. Training in the use of PPE equipment such as fluorescent safety vests/clothing.                                                                                                                                                                                              | Operator<br>Supervisor | <b>2</b>                           |
|                                | Hand, foot & hearing damage, crushing of limbs                                                                 | <b>2</b>   | 1. Training in manual handling & the correct protection, gloves and safety footwear.                                                                                                                                                                                                                                                                                | Supervisor             | <b>3</b>                           |
| 4. Machine Pre Start Check     | Unsafe working conditions. Potential for accident.                                                             | <b>1</b>   | 1. Equipment Prestart checklist forms filled out & defects documented, supervisor notified.<br>2. Ensure windows/ mirrors are clean.<br>3. Ensure all controls are in neutral or park.<br>4. Ensure all gear in the cabin is correctly stored.<br>5. Adjust the seat and use the seat belt.                                                                         | Operator               | <b>2</b>                           |
| 5. Machine Starting checks     | Unsafe working conditions. Increased likelihood of accident during operation.                                  | <b>1</b>   | 1. The operator must be seated and in full control of the machine when starting.<br>2. Check the operation of all of the controls and gauges.<br>3. Listen and watch for defects.                                                                                                                                                                                   | Operator               | <b>2</b>                           |

| Steps in Activity                                 | Potential Hazards                             | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Responsible Person/s                                  | Risk Class After Controls In Place |
|---------------------------------------------------|-----------------------------------------------|------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------|
|                                                   |                                               |            | 4. Test hydraulic functions.<br>5. Ensure all grounded attachments are safely retracted<br>6. Test lights, horn and travel alarm.<br>7. Check safety locking pins in quick hitch are locked for buckets or attachments.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                       |                                    |
| 6. Set out work area and check excavation levels. | Struck by road or construction plant.         | <b>1</b>   | 1. Barricade area off or sign appropriately to restrict access and minimise plant working area.<br>2. All workers to wear full length hi viz clothing.<br>3. Operational flashing lights and reversing beepers.<br>4. All trenches greater than 1.5 metres in depth are to be appropriately shored, benched, battered or otherwise protected from collapse.<br>5. Trenches 1.5 or greater must be accompanied by a suitable rescue/escape plan.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Supervisor<br><br>All Operator                        | <b>2</b>                           |
|                                                   | Striking underground services - electrocution | <b>1</b>   | 1. Before digging starts, make sure you know the exact location of any underground electrical cables, gas lines, water, sewerage and telecommunications cables and Complete a Excavation permit.<br>2. Do not rely solely on site plans and drawings as these are sometimes not accurate or complete.<br>3. Seek assistance from the local services and distribution companies.<br>4. Use "Before you Dig Australia"<br>5. If services are identified in the excavation area non-destructive proving/potholing and marking is required before excavation commences.<br><br><b>Emergency Procedure to be used:</b><br>➤ If the contact point is under the ground there is an area around that point which can be electrified.<br>➤ Jump well clear of that point and move away from the machine and warn others to keep away<br>➤ Stay near the site until help arrives<br>➤ Report the incident to your supervisor immediately who may need to report to WorkSafe. | Supervisor<br><br><br><br><br><br><br><br><br><br>All | <b>2</b>                           |
|                                                   | Persons falling or tripping over on site.     | <b>2</b>   | 1. Maintain good house keeping.<br>2. Barricade off unsafe areas.<br>3. Clearly mark protruding objects using paint, caps or hazard tape.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | All Supervisor<br>Supervisor                          | <b>3</b>                           |

| Steps in Activity                                                        | Potential Hazards                                                                                                                                        | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                         | Responsible Person/s | Risk Class After Controls In Place |
|--------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
|                                                                          | Dust entering eyes                                                                                                                                       | <b>2</b>   | 1. Suppress dust using water truck.<br>2. Eye protection to be worn when required.                                                                                                                                                                                                                                                                                                                                           | Supervisor<br>All    | <b>3</b>                           |
| 7. Excavator operation                                                   | Engine failure                                                                                                                                           | <b>2</b>   | 1. Warm up engine and hydraulic oil before starting work.                                                                                                                                                                                                                                                                                                                                                                    | Operator             | <b>3</b>                           |
| 8. Clearing & grubbing<br>Excavation<br>placement and<br>compaction fill | Striking other objects whilst slewing excavator, materials on the ground flicking up as excavator travels over site.<br>Overbalance of machine at reach. | <b>1</b>   | 1. Be aware of what obstacles are around the site especially when slewing excavator.<br>2. Assess what weights the machine can handle at reach safely before attempting to load trucks.<br>3. Do not carry passengers.<br>4. Keep machine under control at all times.<br>5. Carry the bucket as close to the ground as possible whilst traveling.<br>6. Travel & operate at a safe speed for the operation being undertaken. | Operator             | <b>2</b>                           |
|                                                                          | Attachments or bucket disconnecting from hitch.                                                                                                          | <b>1</b>   | 1. Ensure quick hitch safety pins are engaged whilst bucket or attachments are engaged into quick hitch.                                                                                                                                                                                                                                                                                                                     | Operator             | <b>2</b>                           |
|                                                                          | Release of hydraulic hoses when changing work implements such as tilt bucket, pulverisor, rockbreaker and compaction plate.                              | <b>1</b>   | 1. Ensure hydraulic pressure is taken off hydraulic hoses before releasing couplings. Pressure is normally released if engine is shut down and work tool pedal is pressed back & forth or two way flow ball valve is switched off.                                                                                                                                                                                           | Operator             | <b>2</b>                           |
|                                                                          | Uncontrolled slippage                                                                                                                                    | <b>1</b>   | 1. Assess ground surface conditions eg; wet ground conditions, steep slope.<br>2. When working on top of mound make sure excavator is not taken too close to the edge.                                                                                                                                                                                                                                                       | Operator             | <b>2</b>                           |
|                                                                          | Rockbreaker & pulverizer operation<br>Flying fragments or reo steel from concrete                                                                        | <b>1</b>   | 1. Be aware that fragments can fly from chisel of the rockbreaker, and pulverizer .<br>2. Whilst operating excavator be aware that demolition debris such as reo. and pipe etc... can be flicked up by the tracks and could hit a worker or machine.<br>3. Use eye & hearing protection & keep others well away from work area.                                                                                              | Operator             | <b>2</b>                           |
|                                                                          | Rock & log grab                                                                                                                                          | <b>2</b>   | 1. Material or objects lifted can become insecure due to crumbling or breaking be aware of the different hydraulic pressures that can be applied to objects                                                                                                                                                                                                                                                                  | Operator             | <b>3</b>                           |

| Steps in Activity | Potential Hazards                         | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Responsible Person/s       | Risk Class After Controls In Place |
|-------------------|-------------------------------------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|------------------------------------|
|                   | Compaction plate                          | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Be aware that vibration can effect nearby buildings or unstable ground or trench walls &amp; excavations.</li> <li>2. Assess the situation &amp; surrounding areas that may be affected.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Operator                   | <b>3</b>                           |
|                   | Striking overhead services- electrocution | <b>1</b>   | <p>Operators need to keep;</p> <ol style="list-style-type: none"> <li>1. Clearly mark overhead assets with flagging/signage</li> <li>2. At least 3 metres from 132,000 volt lines.</li> <li>3. At least 6 metres from 132,000 to 330,000volt lines.</li> <li>4. Areas closer than 3m are no go zone.</li> <li>5. Use spotter if working near powerlines. 5. (3m to 6.4m).</li> <li>6. Clarify safe working distances with site manager.</li> <li>7. If in doubt of line voltage keep at least 8 metres away.</li> </ol> <p><b>If your machine makes contact with electrical wires- Refer to Emergency Procedures below and the A5 laminated card in the cabin.</b></p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Operator<br><br>Supervisor | <b>2</b>                           |
|                   |                                           | <b>1</b>   | <p><b>Overhead Wires – Emergency Procedure</b></p> <ol style="list-style-type: none"> <li>1. Stay calm.</li> <li>2. Do not leave your seat.</li> <li>3. Warn others to stay away.</li> <li>4. If possible, try to break contact with the wires, if possible try to lower the bucket without causing further damage to the power lines.</li> <li>5. Make sure that the bucket does not make contact with the ground as this could earth the machine.</li> <li>6. Phone emergency services to have power turned off.</li> </ol> <p>If it is unsafe to stay in/on the machine because the machine is in danger, such as from fire or if you are alone.</p> <ol style="list-style-type: none"> <li>1. <b>Jump well clear onto dry ground if possible, making sure you have both legs together and shuffle with feet together or hop (eg ; kangaroo hop) and hop at least 10 metres away from the machine.</b></li> <li>2. Do not climb down because if you make contact with the machine and the ground at the same time you could be electrocuted.</li> <li>3. If the contact point is under the ground there is an area around that point which can be electrified.</li> </ol> | All                        | <b>2</b>                           |

| Steps in Activity | Potential Hazards                                                                                                                                         | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Responsible Person/s                                                     | Risk Class After Controls In Place |
|-------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|------------------------------------|
|                   |                                                                                                                                                           |            | 4. Jump well clear of that point and move away from the machine and warn others to keep away.<br>5. Stay near the site until help arrives.<br>6. Report the incident to your supervisor immediately who may need to report to WorkSafe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                          |                                    |
|                   | Striking personnel and plant                                                                                                                              | <b>1</b>   | 1. Hold toolbox meeting to discuss hazards.<br>2. All workers to wear full length hi viz clothing<br>3. Where possible minimise plant & personnel in work areas.<br>4. Separate trafficable areas.<br>5. No personnel are to be within the working radius of any plant equipment unless positive comms or visual contact is established with the operator"<br>6. Install giveaway and stop signs where necessary.<br>7. Excavator to have operational flashing light and reversing beeper.<br>8. 'Blind spots' of plant to be identified and discussed with all workers at toolbox meetings.<br>9. Where 'Blind spots' are identified as a potential issue a spotter should be used to minimize hazard.<br>10. Where practicable, plant should always move in a forward direction. | Supervisor<br>All<br>Supervisor<br>Supervisor<br>Supervisor<br>Operators | <b>2</b>                           |
|                   | Exposure to noise                                                                                                                                         | <b>2</b>   | 1. Suppress noise using mufflers.<br>2. Ear protection must be worn by personnel working near noisy equipment.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Workshop<br>All                                                          | <b>3</b>                           |
|                   | Ground failure,<br>Excavation collapse,<br>Sloping ground or<br>Rough unprepared ground,<br>leading to machine rollover<br>and personnel being<br>crushed | <b>1</b>   | 1. Only competent operators to use machinery.<br>2. Operator to complete visual assessment of ground conditions.<br>3. All unbattered excavations to be barricaded off.<br>4. Do not operate close to an overhang or a deep ditch or excavation the weight could collapse the sides of the trench.<br>5. Always approach embankments or trenches from a 90 degree angle.<br>6. Do not use the bucket as a hammer.<br>7. When working on a slope determine whether to dump the spoil on the high side or low side of the trench.<br>8. Adjust the seat and use the seat belt.                                                                                                                                                                                                       | Supervisor<br>Operator<br><br>Supervisor                                 | <b>2</b>                           |

| Steps in Activity | Potential Hazards          | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Responsible Person/s | Risk Class After Controls In Place |
|-------------------|----------------------------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
| 9. Lifting        | Sling failure              | 1          | <ol style="list-style-type: none"> <li>1. The safe working load (SWL) of the machine should be marked on the machine.</li> <li>2. Do not exceed the safe work load and work radius limits of the machine.</li> <li>3. All lifting equipment should be tested and tagged for compliance</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Operator             | 2                                  |
|                   | Struck by moving load/part | 1          | <ol style="list-style-type: none"> <li>1. Check the <b>SWL</b> of the machine and the lifting lugs, slings &amp; chains to ensure the load is correctly slung and balanced and is within the SWL.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Operator             | 2                                  |
|                   | Ground failure             | 1          | <ol style="list-style-type: none"> <li>1. If there is any sign of instability lower the load immediately.</li> </ol>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Operator             | 2                                  |
|                   | Failure during lifting     | 1          | <ol style="list-style-type: none"> <li>1. When the load is raised keep all people at a safe distance.</li> <li>2. Do not swing loads over people's heads.</li> <li>3. Do not leave the load suspended in the air. Lower it as soon as possible.</li> <li>4. Always lower the load to the ground if leaving the machine.</li> <li>5. Make allowances for materials when they are wet. They will weigh more than normal.</li> <li>6. If you do not know the weight of the load do not lift.</li> <li>7. When working on sloping or flat surfaces be aware of the safe bucket capacity eg; rocks falling from an overfull bucket and damaging other items or persons.</li> <li>8. Do not reeve or nip slings around buckets as the sling can be cut by the cutting edge or teeth of the bucket.</li> <li>9. Do not place a sling over a tooth or teeth.</li> <li>10. Place the lifting hook onto the approved lifting lug normally attached to the quick hitch.</li> <li>11. For slinging and lifting of loads where judgement is not required and where the load is always in view of the plant operator a dogger is not required.</li> <li>12. A qualified dogman is to be on site or : <ul style="list-style-type: none"> <li>• Load to always remain in view of the plant operator</li> <li>• Selection of the slinging methods to be pre-determined by a competent person</li> <li>• Lifting points to be pre-determined by a competent person and marked on the load where appropriate.</li> <li>• Weight of the load—or load within a weight range—is pre-</li> </ul> </li> </ol> | Operator             | 2                                  |

|                                                             |                                                                            |          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |          |
|-------------------------------------------------------------|----------------------------------------------------------------------------|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------|
|                                                             |                                                                            |          | determined e.g. may be marked on the load, and suitable lifting equipment (i.e. chains, swift lifts etc.) to be used<br>13. Inspect all slings prior to use. Are they serviceable?<br>14. Refer to SWMS – Using Powered Earthmoving Equipment as a Crane.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |          |
| 10. Traveling equipment on roadway, private or public areas | Damage to roadway or public / private property                             | <b>2</b> | 1. Check ownership of properties or boundaries.<br>2. Travel machine as to avoid disturbance to roadway or public or private lands eg; lift machine to turn on undisturbed areas if required, avoid sharp turns on roadways.<br>3. Be aware of what damage the tracks can do to surfaces.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Operator | <b>3</b> |
| 11. Equipment shut down                                     | Personnel struck by rolling plant                                          | <b>1</b> | 1. Assess parking area as to site vision for other works in the area ( eg traffic situation on roadworks site, avoid parking where vision is blocked).<br>2. Park on firm, level ground where possible.<br>3. Park the machine up and down the slope when parking on a grade.<br>4. Park in a non-operating area.<br>5. Park away from deep excavations and trenches.<br>6. Place the hydraulic lock mechanism in the lock position.<br>7. Lower the bucket or attachment to the ground.<br>8. Idle the engine for gradual cooling before turning it off.<br>9. Move the steering levers back and forward and cycle the hydraulic controls to dissipate residual pressure in the hydraulic system before leaving the machine.<br>10. Remove the ignition key and secure the machine. | Operator | <b>2</b> |
| <b>12. Environmental Issues</b>                             | Transmission of material off site to public domain eg mud or to main road. | <b>2</b> | 1. Where possible endeavor to not park in muddy areas.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Operator | <b>3</b> |
|                                                             | Hydraulic oil spill                                                        | <b>3</b> | 1. Make sure there is a visual check of all hydraulic hoses is part of your prestart check.<br>2. Should there be an extensive oil leak- clean it up immediately.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Operator | <b>3</b> |



| <b>ENVIRONMENTAL RISK ASSESSMENT &amp; CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY</b> |                                                                                                                                                                                                               |                   |                                                                                                                                                                                                                                                                                                                                                                                        |                             |                                           |
|--------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|-------------------------------------------|
| <b>Work Activity Risk</b>                                                                                          | <b>Hazard</b>                                                                                                                                                                                                 | <b>Risk Class</b> | <b>Risk Control Measure</b>                                                                                                                                                                                                                                                                                                                                                            | <b>Responsible Person/s</b> | <b>Risk Class after Controls in place</b> |
| <b>13. Emergencies</b>                                                                                             | Accident/ Incident<br>Fire<br>Spill                                                                                                                                                                           | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring.</li> <li>2. Emergency numbers available on site.</li> <li>3. Fire Extinguishers/First Aid Kits/Spill Kits on site.</li> </ol>                                                                                                         | Supervisor<br>All           | <b>2</b>                                  |
| <b>14. Air Quality</b>                                                                                             | Exhaust Fumes<br>Dust                                                                                                                                                                                         | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures.</li> <li>2. Dampen milled surface with water cart.</li> <li>3. Use water cart where required.</li> </ol>                                                                                                                | Supervisor<br>All           | <b>3</b>                                  |
| <b>15. Bitumen/Prime</b>                                                                                           | During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.                                                                                                       | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Plan prime or bitumen operation so that it is conducted during fine weather.</li> <li>2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly.</li> <li>3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.</li> </ol> | Supervisor<br>All           | <b>2</b>                                  |
| <b>16. Community Relations</b>                                                                                     | Inconvenience as a result of works/traffic management                                                                                                                                                         | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken.</li> <li>2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.</li> </ol>                                            | Supervisor<br>All           | <b>3</b>                                  |
| <b>17. Flora &amp; Fauna</b>                                                                                       | Some works may require the removal of vegetation. Native fauna may be at risk from excavation works                                                                                                           | <b>2</b>          | <ol style="list-style-type: none"> <li>1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage.</li> <li>2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.</li> </ol>                                                                              | Supervisor<br>All           | <b>3</b>                                  |
| <b>18. Heritage &amp; Archaeology</b>                                                                              | Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance | <b>1</b>          | <ol style="list-style-type: none"> <li>1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist.</li> <li>2. Develop a project specific procedure based on the findings and recommendations.</li> <li>3. Installation of exclusion fencing and signage if required.</li> </ol> | Supervisor<br>All           | <b>2</b>                                  |

| Work Activity Risk                                                 | Hazard                                                                                                                                                                                                                                                                                                                 | Risk Class | Risk Control Measure                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Responsible Person/s | Risk Class after Controls in place |
|--------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|------------------------------------|
| <b>19. Noise Pollution, Community Relations &amp; Vibration</b>    | Sensitivity to noise - to public & fauna                                                                                                                                                                                                                                                                               | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Work undertaken during “normal” hours where possible.</li> <li>2. Affected residents notified in person or in writing.</li> <li>3. Plant and equipment regularly serviced &amp; fitted with efficient mufflers.</li> <li>4. Magnitude of vibration reduced by using smaller plant etc.</li> </ol>                                                                                                                                                                                                                                                                                     | Supervisor<br>All    | <b>2</b>                           |
| <b>20. Soil Management &amp; 21. Water Quality</b>                 | Soil needs to be managed to ensure that; there are no off-site impacts.<br>Damage to stockpile areas (not prepared properly).<br>Mud deposited onto roadways.                                                                                                                                                          | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Wash down machinery in only nominated areas.</li> <li>2. Not within 20 metres of water courses.</li> <li>3. Use only approved and nominated stockpile areas.</li> <li>4. Build bund wall out of material available on site.</li> <li>5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.</li> </ol>                                                                                                                                                                                                                    | Supervisor<br>All    | <b>3</b>                           |
| <b>22. Fuels and Chemicals</b>                                     | Contamination of waterways due to spillages of oil, degreasers, diesel, etc.                                                                                                                                                                                                                                           | <b>1</b>   | <ol style="list-style-type: none"> <li>1. Store fuel and chemicals in accordance with relevant standards/guidelines.</li> <li>2. Minimise storage on site and locate storage facilities away from drains and waterways.</li> <li>3. All containers clearly labelled and Safety Data Sheets are available on site.</li> <li>4. All drums stored securely and in a bunded area.</li> <li>5. Spill kits or alternative spill containment materials available on site.</li> <li>6. Regular maintenance of plant hoses.</li> <li>7. Use correct refuelling equipment.</li> </ol>                                                     | Supervisor<br>All    | <b>2</b>                           |
| <b>23. Visual Impact 24. Litter and Amenities Waste Management</b> | Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive.<br>Production generated lighting, litter, mud, dirt and dust may also impact residents. | <b>2</b>   | <ol style="list-style-type: none"> <li>1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents.</li> <li>2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately.</li> <li>3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site.</li> <li>4. Broken-out paved surfaces shall be repaired as soon as possible.</li> <li>5. Remove all rubbish from site each day.</li> <li>6. Waste asphalt will be recycled where possible.</li> </ol> | Supervisor<br>All    | <b>3</b>                           |

| <b>Personal Protective Equipment</b>                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|------------------------------------------------------|-------------------------------------------------------------------------------------------------|---------------------------------|
| All site personnel must wear the required PPE specified in the controls above, such as:                                                                                                                                                                                                                                                                                                                                |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| Safety Hi-vis<br>Vests/Shirts                                                                                                                                                                                                                                                                                                                                                                                          | Safety Boots                                                                                                                           | Sunscreen                                             | Broad Brimmed<br>Sun Hat                                                                                            | Sunglasses                                           | Gloves specific to the task                                                                     | White reflective overalls/night |
| Hard Hat where<br>required                                                                                                                                                                                                                                                                                                                                                                                             | Safety Glasses                                                                                                                         | Hearing protection<br>where required                  | Long clothing                                                                                                       | Dust masks                                           | Respiratory equipment if<br>required                                                            |                                 |
| <b>Workers may require Task Specific Training depending on activity each worker will be required to fulfill.</b>                                                                                                                                                                                                                                                                                                       |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <ul style="list-style-type: none"> <li>All workers shall hold a current Construction Induction Card</li> </ul>                                                                                                                                                                                                                                                                                                         |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <ul style="list-style-type: none"> <li>If required Client Site Induction</li> <li>Activity Induction (SWMS &amp; SWP's)</li> </ul>                                                                                                                                                                                                                                                                                     | <ul style="list-style-type: none"> <li>Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)</li> </ul> |                                                       | <ul style="list-style-type: none"> <li>Plant Operators licences or competency assessments where required</li> </ul> |                                                      | <ul style="list-style-type: none"> <li>Competencies for Work Zone Traffic Management</li> </ul> |                                 |
| <ul style="list-style-type: none"> <li>First Aid certificate training</li> </ul>                                                                                                                                                                                                                                                                                                                                       | <ul style="list-style-type: none"> <li>Manual Handling training</li> </ul>                                                             |                                                       | <ul style="list-style-type: none"> <li>Fire Extinguisher training</li> </ul>                                        |                                                      | <ul style="list-style-type: none"> <li>Fatigue Management Training</li> </ul>                   |                                 |
| <b>A Site Specific Induction &amp; Toolbox Meeting will be held each day prior to the start of each job.</b>                                                                                                                                                                                                                                                                                                           |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <b>Legislation &amp; Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)</b>                                                                                                                                                                                                                                                                             |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <b>Codes of Practice</b>                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| Confined Spaces - 2020                                                                                                                                                                                                                                                                                                                                                                                                 | Hazardous Manual Tasks - 2020                                                                                                          | Managing Noise & Preventing Hearing Loss at Work-2020 |                                                                                                                     | Managing Risks of Plant in the Workplace - 2018      |                                                                                                 |                                 |
| Construction Work - 2020                                                                                                                                                                                                                                                                                                                                                                                               | How to Manage WH&S Risks - 2018                                                                                                        | Managing Risk of Falls at Workplaces - 2020           |                                                                                                                     | Managing Electrical Risks in the Workplace -2019     |                                                                                                 |                                 |
| Excavation Work - 2020                                                                                                                                                                                                                                                                                                                                                                                                 | First Aid in the Workplace - 2018                                                                                                      | Managing Work Environment & Facilities - 2020         |                                                                                                                     | WHS Consultation Co-operation & Co-ordination - 2018 |                                                                                                 |                                 |
| Welding Processes - 2021                                                                                                                                                                                                                                                                                                                                                                                               | How to Safely Remove Asbestos - 2020                                                                                                   | Managing Risk of Hazardous Chemicals - 2018           |                                                                                                                     | Safe Design of Structures - 2018                     |                                                                                                 |                                 |
| <b>Plant &amp; Equipment for this activity</b>                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <ul style="list-style-type: none"> <li>All plant is inspected prior to sending out to site</li> <li>Daily maintenance &amp; service checks.</li> <li>Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out.</li> <li>Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.</li> </ul> |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <b>List of plant for this Activity</b>                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
|                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |
| <b>Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):</b>                                                                                                                                                                                                                                                                                                             |                                                                                                                                        |                                                       |                                                                                                                     |                                                      |                                                                                                 |                                 |

**Implementation, Monitoring and Review of SWMS**

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

**SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS**

| Name (please print clearly) | Signature | Company | Date |
|-----------------------------|-----------|---------|------|
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |
|                             |           |         |      |

**Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.**