



SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods , plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	CABLE HAULING	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Signature: _____ 			
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> Phone	<u></u> Signature
			<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training and skill.	Un-trained persons could cause injury to themselves and others.	1	1. All persons working on a site must carry with them a current 'Construction Induction Card (Red Card or equivalent). 2. All persons working on site must be suitably trained and competent in the task they are to perform. 3. All persons on site to attend site induction as required by client. 4. All works to be completed in accordance with current Australian Standard.	Management	2
Scope of Works	Cabling incorrect area	1	1. Obtain information from the clients for scope of works eg the to and from destination for the cable hauling like a building number/address etc. • Read and interpret plan to ensure that the required result is attainable. • Check availability of cable in order that work may be programmed. • Obtain cable as specified in the plan. 2. Conduits need to be identified for example - Telstra have multiple conduits available so they are numbered A1, A2 , A3. 2nd layer in 6 conduit run would be B1,B2,B3 or the pits would be numbered with BLD No , BLD 440 to Pit 570 to pits 571,572,73 etc end at building 513 for example.	Supervisor	2
Pre start toolbox meeting	Personal injury	1	1. Supervisor to conduct a Pre start- toolbox meeting to identify potential hazards and implement control measures to mitigate risks to workers. 2. The Supervisor will also discuss the job and the plans noting correct destination, building access, correct cable & length etc. 3. Make sure we have adequate personnel to roll out the cable runs. 4. Erect signage where required to prevent unauthorized access to cable hauling areas.	Supervisor	2
Check area for other services and confirm locations of any gas lines, power cables etc	Electrocution Gas explosion	1	1. Ensure location of other services is confirmed and appropriate access permits obtained	Supervisor	2
Personal Protective Clothing & Equipment	Personal injury	1	1. Before starting work on site check available PPE is adequate for all tasks to be under taken and in good working condition.	Supervisor	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Vehicle access	Vehicle Collisions with other workers or pedestrians.	1	1. Comply with speed limits on and around site. 2. Drive only in designated access routes. 3. Do not park vehicles where it will create a hazard to public vehicles, pedestrians or other workers. 4. All persons are to keep completely clear of delivery areas until delivery is complete. 5. High visibility shirts/vests to be worn. 6. If required to work near vehicles a barricaded zone will be necessary.	Workers	2
Personnel access	Trip, slip hazards.	2	1. Clear any obstacles from around all work areas before and as work progresses. 2. Keep pathways clear of trip hazards.	Workers	3
Prepare for underground cable hauling	Stress on cables	2	1. Rod the cable route, pull in rope for cable hauling, rope to match cable size. 2. Designate the hauling start point at say pit 570 with enough room to lay out cables in a figure eight configuration on the ground for hand hauling or drums on stands to pull cables through to next pit, making sure no stress on cables, keep distance hauled to say 2-300 metres in length. 3. Place guards around open manholes.	Supervisor Workers	3
Hauling cable	Handle cables in a manner that avoids cable damage	2	1. Do NOT put too much pressure on cable, avoid stretching, kinks etc. 2. Hauling lengths must be in a straight line not to haul around bends that will create pressure when laying out cable by hand it must be put into figure of 8 on the ground to haul to next pit or say a pit 200- 300 metres away would be fine in a straight line. 3. Use aids such as cable protection devices, slippers in pipe to assist drag on cable & protection in pits/manholes. 4. Personnel can be placed at intervals and use communications like UHF radios to maintain constant contact. 5. STOP if cable grabs etc.	Supervisor Workers	3
General Safety Issues that may occur on site	Manual handling disorders.	2	1. Physical fitness and warm up exercises will assist in avoiding manual handling injury. 2. Only carry what is a comfortable weight and do not overload yourself. 3. Bend your knees when lifting not your back. 4. Rotate jobs.	Supervisor Workers	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Cuts, abrasions from hand tools	2	1. Ensure tools are inspected prior to use and are in good order.	Workers	3
	Exposure to noise from power tools	2	1. Wear hearing protection where required.	Workers	3
	Possibility of electrocution from power tools.	1	1. Choose battery powered tools in the first instance. 2. Make sure electrical tools have been tested and tagged.	Workers	2
	Sunburn	1	1. Workers to wear long pants, long sleeves, sun hats, sunscreen as per 'Personal protective equipment' procedure.	All	2
	Heat Stress	2	1. Management assess the environment during the day and put in place heat stress management techniques such as ensuring workers drink sufficient cool water, take regular breaks & shade covers provided where practicable.	Supervisor	3
Environmental Issues	Potential hazards to the environment – flora, fauna etc	1-3	1. Prior to start of works and during works potential environmental hazards are to be recognised and controls put in place to eliminate the risk. Follow guidelines set down in the company Environmental Management Guidelines.	Supervisor All	2-3
Complete works on site	Trip hazards etc	2	1. Site is reinstated and left safe, tools and materials are stored in accordance with enterprise guidelines 2. Waste materials and lubricant spills cleaned up as required.	Supervisor	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste products will be recycled where possible.	Supervisor All	3

Personal Protective Equipment

All site personnel must wear the required PPE specified in the controls above, such as:

Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	

Workers may require Task Specific Training depending on activity each worker will be required to fulfill.

All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)	Plant Operators licences or competency assessments where required	Competencies for Work Zone Traffic Management			
First Aid certificate training	Manual Handling training	Fire Extinguisher training	Fatigue Management Training			

A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.

Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)

Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022

Codes of Practice

Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020	Managing Risks of Plant in the Workplace - 2018
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020	Managing Electrical Risks in the Workplace -2018
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020	WHS Consultation Co-operation & Co-ordination - 2018
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018	Safe Design of Structures - 2018

Plant & Equipment for this activity

- All plant is inspected prior to sending out to site
- Daily maintenance & service checks.
- Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out.
- Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.

List of plant for this Activity

Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.

WORK ACTIVITY BRIEFING**Implementation, Monitoring and Review of SWMS**

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.