


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman:	Date:	
High Risk Construction Work:	MANUAL HANDLING	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Signature: 			
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> Phone	<u></u> Signature
			<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Confirming where the item to be lifted/moved is able to be safely relocated to, pathway is clear and free from obstacles, hazards and risks.	Item is too large or ill fitting to be placed at the desired end location and need to be returned. Pathway has trip or other hazards		1. Clear the		
Lifting an object	Object could be awkward, heavy, loosely packaged, hot, cold, sharp edged or slippery. Object could be unstable.	2	2. Carefully assess the object to be lifted. 3. Use mechanical aids if possible 4. Always seek help with lifting an object if needed. 5. Don't lift an object that is too heavy, awkward or unbalanced.	Management Supervisor Operator	3
Push or pull an object	Surface could be wet, rough, ridged, slippery or sloping. Object could be heavy, sharp, hot or cold, slippery or loosely packaged. Object could be unstable.	2	1. Carefully assess object to be moved and move it cautiously. 2. Use mechanical aids if possible. 3. Seek help with push or pull if needed. 4. Ensure grip of your footwear is adequate.	Management Supervisor Operator	3
Erecting an object	Object might be unstable, move and/or fall. Object could be slippery to handle, have sharp edges, may be heavy, awkward, hot or cold.	2	1. Assess the object to be erected and carefully plan the erection process so as to avoid accidents. 2. Seek advice if unsure.	Management Supervisor Operator	3
Holding or supporting an object	Object could be unstable, heavy to support, slippery or sharp. A person in a static position supporting a weight manually for any length of time could sustain an injury.	2	1. Try where possible to use a mechanical method of supporting the object. 2. If an object has to be supported manually, carefully plan the task before commencing the supporting process.	Management Supervisor Operator	3
Using heavy tools	In awkward and confined working positions, supporting heavy tools can lead to injury.	1	1. Where possible seek help from a fellow worker to support the tool or mechanically support the tool using a tool-lifting device.	Management Supervisor Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Bending and stooping	Bending and stooping while working will put strain on your lower back especially if lifting or moving an object.	2	1. Squat where possible; keeping your legs bent and back reasonably straight. 2. If there is a need to bend or stoop ensure you straighten your body regularly. 3. Avoid bending or stooping as much as possible.	Supervisor Workers	3
Twisting one's body	Twisting one's body while lifting can cause low back injuries especially if lifting an object or restraining a load	2	1. Avoid twisting at all times when supporting or restraining a load or lifting or pushing or pulling an object. 2. Move your feet rather than twist your body.	Supervisor Workers	3
Repetitive work	Repetitive work for long duration's may lead to back injury when lifting, pushing or pulling an object, bending and/or twisting your body.	2	1. Ensure short rest breaks are taken often. 2. Where possible share the repetitive task with another person and alternate your work tasks.	Supervisor Workers	3
Using tools that vibrate	Extended periods of vibrations to one's hands can cause White Finger and damage the nerves of the hands.	2	1. Use padded gloves especially designed to absorb vibrations. 2. Take regular breaks by sharing the task with other workers. 3. Where possible insulate yourself from the vibrations by mechanical or other means.	Supervisor Workers	3
Digging and shoveling	Sudden unexpected body movements and /or twisting motions caused by digging or shoveling actions can cause back injuries.	2	1. Avoid unexpected body movements. 2. Where possible use mechanical methods for digging. 3. Avoid twisting your body by moving your feet when shoveling.	Supervisor Workers	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.