


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman:	Date:	
High Risk Construction Work:	Horizontal Directional Drilling (HDD) Unloading & Operation	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025 SWMS Review Date: April 2026 unless required earlier		Location:	
Signature: _____ 			
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> Phone	<u></u> Signature
			<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment
The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Training and skill.	Un-trained persons could cause injury to themselves and others. Possible property damage.	1	1. All persons on site must carry with them a current 'Construction Induction Card'. 2. Truck drivers must hold a Heavy Vehicle Drivers License 3. No person shall operate mobile plant or the drill without the appropriate license or competency assessment. 4. Operators to have attended Plant Overhead Electrical Course.	Management Drill Operator	2
Personal Protective Clothing & Equipment (PPE)	Personal injury.	1	1. Minimum PPE to be worn on site is: • Hi visibility vests/clothing • Steel toe-capped boots • UV skin protection minimum 15+ UV sunscreen • Head protection as applicable • Long pants and long sleeves where applicable.	Truck Driver Drill Operator	2
Traffic management On roadside or Worksite.	Various injuries from collision with traffic or other plant. Pedestrians could be injured if they intrude into loading/unloading area.	1	1. Traffic management is to be provided where required by the Supervisor or the Contractor. 2. Persons not involved in unloading of plant to be kept clear of the area at least 10m. 3. All Drills, floats and trucks to have operating reversing beepers and flashing orange lights. 4. Truck controller to be used as required eg where there is restricted rear vision.	Supervisor Drill Operator	2
Site Access	Various injuries from collision with traffic or other plant. Possible property damage.	1	1. Comply with speed limits on and around site. 2. Drive only in designated access routes. 3. Do not park vehicles where it will create a hazard to public vehicles, mobile plant, pedestrians or other workers. 4. Park on level ground. 5. Limit reversing on site where possible & use a truck controller where required.	Truck driver Drill Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Hitching tow vehicle to trailer or low loader	Property damage and/or personal injury. Possible crushing injuries from breakaway of trailer or low loader. People. Traffic. Night (Darkness).	1	1. Attach tow couplings securely to towing vehicle (as there are so many different types of tow hitches and couplings ensure you have been shown how to correctly secure the type you use). 2. Use lock pins and safety latches where provided. 3. Attach all breakaway safety chains securely to towing vehicle. 4. Inspect tow coupling and safety chains before use; do not rely on bystanders to secure tow couplings and safety chains. The driver is responsible for securing the tow coupling. 5. Do not tow or use vehicles or plant with faulty tow couplings or safety chains, report faults to your manager immediately. 6. Ensure to connect the braking and light systems correctly. 7. Check all lights and braking systems prior to loading plant/equipment. 8. It is the driver's responsibility to ensure the trailer is secured correctly. 9. Ensure reversing beeper is working. 10. Use mirrors when reversing. 11. Turn on revolving flashing light. 12. Use spotlight, which is mounted at the rear of the cab, to help visibility at night.	Truck Driver Drill Operator	2
Check tyres, light and brakes etc.	Traffic.	1	1. Wear a high visibility vest when walking around the float inspecting the tyres, lights etc. (IMPORTANT: White overalls with retro-reflective tape must be worn at night; or reflective vest over overalls).	Truck Driver Drill Operator	2
Travel to pick up/drop off location	Traffic. People.	1	1. As a professional driver, drive truck in accordance with the Heavy Vehicle's Drivers License. (Roads & Maritime Services Road Rules).	Truck Driver Drill Operator	2
Look for suitable location to park to load/ unload.	Traffic. People. Overhead power lines. Overhanging tree branches. Residential Areas. Uneven ground. Wet weather.	1	1. Park at a safe distance away from street corners and avoid narrow streets. 2. Park at a safe distance from low lying power lines and overhanging tree branches. N.B. Be cautious of height issues. 3. Avoid early morning shifts in residential areas if possible. 4. Avoid confrontations with the public and report all complaints. 5. Park on firm level ground. 6. Avoid dirt areas, which may become boggy during wet weather.	Truck Driver Drill Operator	2

Traffic Control Devices (If Traffic Control not on Site)	Traffic. People.	1	1. Place speed limit signs out at appropriate distance as stated in the selected Generic TMP 2. Cover any existing speed limit signs and place traffic cone beneath the covered sign 3. Place traffic cones around all trucks, plant & equipment 4. Place traffic cones and, if necessary, extendable tiger tailed sticks around proposed unloading site	Drill Operator	
---	---------------------	----------	---	----------------	--

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Lower/raise ramps/tilt tray and put legs stabilizing legs in place.	People. Traffic. Objects.	1	1. Make sure area is clear of any objects or persons prior to lowering ramps. 2. Move truck forward and look for a more suitable location if ramps are not sitting level on ground.	Truck Driver Drill Operator	2
Check drill to be transported.	Vandalism to machines. Theft.	1	1. A pre-transport check of brakes, tracks, etc is carried out visually. 2. Obvious visual problems such as worn tracks, cut hydraulic hoses, engine covers off machined etc, can generally be picked up by the driver. REPORT ALL OBVIOUS DAMAGE. 3. It is important to report when machines are found "unlocked".	Truck Driver Drill Operator	2
Loading or Unloading Plant or Equipment	Various injuries and or property damage. Traffic people	1	1. Persons not involved in loading or unloading of plant/equipment to be kept clear of the area at least 10m in case the load falls or topples from the trailer or float. 2. Load and unload on stable, level ground, using the pendant control externally (if available), persons are not permitted within cabin when loading/unloading large HDDs. 3. Apply the brakes of the transporter/tilt tray and chock its wheels to prevent movement when required. 4. Make sure that portable loading ramps, tilt tray are reasonably clean, firm, secure, and in line with the deck.	Supervisor Truck Driver	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
			5. Carefully line up the drill with the ramp and float, tilt tray. 6. Use low gear only when loading/unloading drills. 7. Position the drill so that its weight is correctly distributed on the float/tilt tray. 8. When loading disabled drills or heavy plant with winches, take care that the winch speed is low enough for the operator of the machine being loaded to maintain control of the drill. 9. When side loading, ensure that blocks are placed under both sides of the float to prevent swaying. 10. If someone is assisting to load drill they must be ticketed/competent in the plant they are driving and you need to make sure you are both familiar with the hand signals used in the loading and unloading of machines. 11. Avoid parking machines on slopes.		
	Wet weather	1	1. Be careful when loading in wet weather because the deck can be slippery. 2. Use timber or conveyor rubber on deck when loading steel on steel. 3. Use wet weather gear supplied.	Truck Driver Drill Operator	2
Secure plant/equipment	Machines could become dislodged and fall from low loader which would create a major hazards for traffic, people and / or property. Using the older style dog (anchor type) can be awkward and dangerous to the low loader driver and the public.	1	1. Ensure that the drill is lashed/chained in accordance with the recommendations in the "load restraint guide". 2. Ensure chains and load binders ("dogs") are in good condition, (replace and / or report when new chains / dogs are required). 3. Use the correct number of chains and dogs for the load configurations to be floated. Always keep a tally as to the number of chains used during a float shift. This will help reduce the number lost during float moves. 4. Ensure the machines are tied down using the appropriate "tie – down" locations.	Truck Driver Drill Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
	Crushing injuries including hands & feet from improperly loaded Equipment, wedging of the body between truck tray & the load.	1	1. Personal care must be taken at all times & wearing of appropriate PPE to limit exposure to crushing, gloves, hard hat when required & steel capped boots to be worn. 2. Loads to be secured at all times. 3. Load binders, straps, chains & load dogs to be inspected before use. Use only approved lifting chains & or slings in good condition. 4. Truck mounted cranes & or tilt trays are only to be used also on a firm level surface with outrigger legs fully extended. 5. Do not use cranes or winches to secure load. 6. Never stand between load and truck tray.	Truck Driver Drill Operator	2
	Exposure to electric shock from chains, equipment, truck mounted crane & or tilt tray coming into contact with live power lines.	1	1. Exercise extreme care when using chains, truck mounted crane or tilt tray, keep the minimum distance away from any power line. Before loading, tying down, lifting or tilting operations LOOK UP for power lines.	Truck Driver Drill Operator	2
	Falling, tripping & slipping from tray of truck or float.	1	1. Personal care must be taken at all times & wearing of appropriate PPE including rubber soled & steel capped boots. 2. Access vehicle tray via fitted step ladders and access ramps, do not jump from truck trays. 3. Do not jump from trailer to ground – climb down safely maintaining 3 points of contact at all times.	Truck Driver Drill Operator	2
	Head Injuries from contact with load or chains & slings.	1	1. Personal care must be taken at all times & wearing of appropriate PPE including hard hat.	Truck Driver Drill Operator	2
	Manual handling injuries.	1	1. Take care when moving ramps and if an item is too heavy or awkward as for assistance.	Truck Driver Drill Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Environmental Issues	Transmission of material off site, eg mud or spread noxious weeds from truck tyres.	2	1. Where possible endeavor to not park in muddy areas. 2. Where a Tyre wash system has been set up by the principle contractor then it should be used.	Truck Driver Drill Operator	3
	Dust/dirt on low loader deck after unloading.	3	1. Sweep deck with broom to avoid material blowing off onto vehicles / traffic.	Truck Driver Drill Operator	3
Lock Machines	Vandalism Theft of machines	1	1. Drivers to secure all machines properly with the padlocks supplied.	Truck Driver Drill Operator	2
Site security; un-authorised access.	Possible injury to un-authorised persons entering the work depot.	2	1. Close gates etc. on departure where applicable.	Truck Driver Drill Operator	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Prior to entering Drill	Striking underground Infrastructure	1	1.Ensure Paneltec SWP 22 HDD site survey has been carried out 2.If it hasn't conduct survey and obtain all relevant locations & mark up 3.Ensure DBYD is up to date and accessible on-site 4.Review all DBYD infrastructure drawing before entering cabin	Drill Operator	2
Personal Protective Clothing & Equipment (PPE)	Personal injury.	1	Minimum PPE to be worn on site is: 1. Hi visibility vests/clothing 2. Steel toe-capped boots 3. UV skin protection minimum 15+ UV sunscreen 4. Head protection as applicable 5. Long pants and long sleeves	Truck Driver Drill Operator	2
Cordon off site area from potential inadvertent access	Injuries to public, or other persons from collision with traffic or other plant.	1	1. Place traffic cones around the operational area in a 360-degree field a round the drill 2. Place extendable tiger tailed sticks over traffic cones in areas where it is not safe for entry (excavation, near drill rack) 3. Re check all traffic signs are still in the appropriate place from unloading and still in correct position for safe drill operation	Drill Operator	2
Entering the Drill	Various injuries to operator from using wrong entry techniques	1	1. Ensure 3 points of contact is maintained when entering the drill grasping the hand support rails fitted inside the cabin 2. When entering cabin, it is recommended that the main cabin is pivoted away from the main drill rack as far as possible 3. Where it is not possible to pivot the cabin away from the drill rack on entry extra precautions must be applied to avoid crushing injuries from drill rack (isolation etc).	Drill Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls in Place
Operating the Drill	Crush hazards, roll over, striking underground infrastructure	1	1. The operator of the drill must be appropriately trained and experienced in the operation of the drill that is being used 2. All operations of the drill must be in accordance with the training received that is specific to that drill 3. All pre-work documentation (HDD survey, JSEA/SSRA) and DBYD review must have been completed before the drill begins operation. 4. Before operating the drill, the operator must ensure that all emergency stops are operational internal and external.	Drill Operator	2
	Striking Underground Electrical Infrastructure	1	1. The drill is equipped with a strike alert should the drill head or rods make inadvertent access with underground power. 2. In the event the strike alarm does sound the operator must remain Seated within their cabin and avoid touching any metal components 3. The operator must remain within the cabin until the power company arrives on site 4. If necessary due to fire, the operator must kangaroo jump as far as possible away from the drill avoiding all water or metallic items.	Drill Operator	2
	In the instance of any of the risks occurring across, consult their direct line manager or compliance manager immediately.	1	Some of the major potential risks associated with HDD operations are listed below. The competent person shall inform their direct line manager or compliance manager in the event of any of the following occurring: 1. Failure to complete the bore or pullback operation successfully 2. Injury to any worker or member of the public 3. Degradation of environmental, natural, historical or cultural resource 4. Collapse or subsidence of the surface or adjacent underground plant 5. Heaving or humping of the surface or damage to structure or roadways 6. Inadvertent fluid returns 7. Striking existing underground infrastructure 6. Significant deviation from the proposed drill path profile	Drill Operator	2

	Drilling in protected environments	2	There are a number of unless agreed sites where drilling is not allowed. These relate to certain types of locations, premises, underground services, structures, etc., along the proposed route. Although not exhaustive, the following list indicates some situations where the use of HDD may not be appropriate and shall be considered: • Instances where relevant authorities will not allow HDD • Inside or within 50 m of the boundaries of hydro power stations, above ground installations and natural gas let down stations (offtake stations) • Within 100m of the known location of TGP and other transmission pipelines • Within 10 m of oil cooled electric cables and electric stations/sub-stations where their underground plant exits • Near public or multi-occupied buildings/premises where cellars, basements, personnel or service corridors/tunnels protrude from the building line, for example hospitals; schools; office blocks; cinemas; theatres; shopping malls/buildings; high rise flats; DOH establishments, etc. • Within areas of environmentally sensitive sites, rivers, watercourses, listed • Within the boundary of airports and docks • Heritage buildings, archaeological sites or protected trees, plants and animals without authorization from the EPA or relevant department. • Contaminated sites where Town Gas is present, or PE pipe material may degrade once laid such as landfill sites	Operations Manager Supervisor Drill Operator	3
--	------------------------------------	---	--	---	---

Exiting the Drill	Various injuries to operator from using wrong entry techniques	1	1. Ensure 3 points of contact is maintained when exiting the drill grasping the hand support rails fitted inside the cabin 2. When exiting the cabin, it is recommended that the main cabin is pivoted away from the main drill rack as far as possible 3. Where it is not possible to pivot the cabin away from the drill rack on entry extra precautions must be applied to avoid crushing injuries from drill rack (isolation etc).	Drill Operator	2
Packing up the Drill and Loading the Drill		1	1. Reverse all procedures in unloading the drill. 2. If contamination is evident on site (flora/soil) wash the drill and plant down on site, prior to loading. 3. The is traffic signs and traffic cones must stay in place until the drill is secured and you are ready to depart site.	Truck Driver Drill Operator Supervisor	2

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Bitumen/Prime	During heavy rain, recently placed prime or bitumen could emulsify and wash into surrounding waterways.	1	1. Plan prime or bitumen operation so that it is conducted during fine weather. 2. Have material available to clean up a spill if it occurs and dispose of contaminated material accordingly. 3. Protect storm drains during and after application to prevent pollution - have spill clean-up materials available.	Supervisor All	2
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during “normal” hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste asphalt will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.