


SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	JACKHAMMER - SAFE OPERATION	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group -Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	 Signature
			<u>31/08/2025 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L Likely	M Moderate	U Unlikely
H (1) (High level of harm)	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) (High)	1	1	2
M (2) (Medium level of harm)	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) (Medium)	1	2	3
L (3) (Low level of harm)	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) (Low)	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training and skill.	Un-trained persons could cause injury to themselves and others. Possible property damage.	2	1. All persons on site must carry with them a current 'Construction Induction Card'. 2. All persons working on site must be suitably licensed, trained and competent in the work they are to perform.	Management	3
Personal Protective Clothing & Equipment (PPE)	Personal injury.	2	1. Minimum PPE to be worn on site is: • Hi visibility vests/clothing • Steel toe-capped boots • UV skin protection minimum 15+ UV sunscreen • Head protection as applicable • Hearing Protection • Safety goggles	All	3
Set out work area	Injury to public Slipping & Tripping	2	1. Prevent pedestrian access using closed gates or barriers where necessary 2. Ensure work area is clear of obstacles. 3. Mark protruding object with yellow paint or tape of area.	Operator	3
	Hearing & eye damage to other workers	2	1. Set up exclusion zones to prevent unauthorized persons from entering work area. 2. Advise nearby workers of the availability of ear plugs if required for short term exposure to noise.	Operator	3
	Fumes from compressor Noise form compressor	2	1. Ensure compressor is in an open ventilated area and that fumes will not affect other workers, avoid positioning compressor near areas where other workers are working. 2. Ensure all doors are closed while compressor is in use	Operator	3
Set up air compressor and Jackhammer	Machinery breakdown or malfunction	2	1. Complete pre start checklist for compressor & safety check of jackhammer. 2. Follow guidelines for SWMS - Safe Operation of Compressed Air.	Operator	3
	Machinery noise	2	1. Hearing protection to be worn in vicinity of equipment.	Operator	3
	Personal injury	2	1. PPE to be worn by all operators - Hard toe boots, Hearing protection. 2. Do not point compressed air at one's body, clothing or another person.	Operator	3
	Hose blow out	2	1. Ensure that appropriate pins are used to secure all hose fittings, compressor is not to be started until this is confirmed. 2. Prior to starting compressor ensure that all hoses are in good condition, any defective hoses should be put away and marked danger do not use.	Operator	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Compressed air outlets may cause injuries if turned on.	2	1. Ensure all valves are turned off prior to starting compressor.	Operator	3
	Cuts to hoses causing blow outs	2	1. Ensure that all hoses are located to ensure that they cannot be damaged by plant running over them or by sharp objects in the path of the hoses. If it is necessary to run compressor hoses across a trafficable access way protection may be required for the hose by way of appropriately sized timber running on either side of the hose.	Operator	3
Use jack hammer	Personal injury Electrocution	1	1. Always disconnect the electric power or air supply before inserting or removing tools. 2. Be sure all tools are properly locked into the unit before operating. 3. If stopping work for a short period of time or for the day, turn off & unplug the electricity.	Operator	2
	Electrocution or explosion from striking live services	1	1. Liaise with supervisor to ensure that no live services are in the vicinity of work. 2. Dial ' Before U Dig' should be used where appropriate.	Operator	2
	Back Injury	1	1. Warm up before work. 2. Observe manual handling techniques. 3. Workers to be trained in proper use of jack hammer, using the knee as a lever to minimise lifting. Proper use will minimise any risk of back injury. 4. Use the correct hammer for the application, too large a hammer means unnecessary weight, a hammer that is too light will require more effort and take longer to do the job. 5. Use appropriate length chisel or point to minimise bending whilst using the hammer. 6. Allow the tool to do the work by using a grip light enough to maintain control. 7. Take rest breaks as needed.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Injury to feet from hammer striking foot	2	1. Always keep feet clear of hammer	Operator	3
	Hearing damage	2	1. Always wear hearing protection whilst jack hammering.	Operator	3
	Eye injury	2	1. Eye protection must be worn whilst using jack hammer.	Operator	3
Other hazards	Sunburn may cause skin damage.	1	1. Workers to wear long pants, long sleeves, sun hats and sunscreen as per WH&S procedure.	All	2
	Heat Stress	2	1. Management to assess the environment during the day and put in place heat stress management techniques such as ensuring workers drink sufficient cool water, take regular breaks & shade covers provided where practicable.	Supervisor	3
Identifying additional daily hazards	Could be Various	Vary 1 to 3	1. Prior to the start of the day a site hazard assessment will be completed.	Supervisor	2-3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it affects them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for buildup of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled, and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refueling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste products will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.