

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods , plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	STREET SWEEPER - SAFE OPERATION	Project:	
SWMS prepared by Patrick Monaghan - Paneltec Group - Operations Manager and in consultation with management and workers – 2025 SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	<u>31/08/2024 – V12.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training and skill.	Un-trained persons could cause injury to themselves and others. Possible property damage.	1	1. All persons on site must carry with them a current 'Construction Induction Card'. 2. All persons working on site must be suitably licensed, trained and competent in the work they are to perform. 3. No person shall operate a street sweeper without the appropriate licence or competency assessment. 4. All work is carried out as directed by the Supervisor, Foreman or customer representative.	Management	2
Personal Protective Clothing & Equipment (PPE)	Personal injury.	1	1. Minimum PPE to be worn on site is: • Hi visibility vests/clothing • Steel toe-capped boots • UV skin protection minimum 15+ UV sunscreen • Head protection as applicable eg sun/hard hat • Long pants and long sleeves 2. Seat belt to be worn at all times.	Operator	2
Pre Start Check	Serious injury, damage	1	1. Operator must inspect the machine and ensure it is in proper working condition, all fluids at correct level, with all necessary guards in place and correctly adjusted. 2. Pre start checklist forms filled out & defects documented, notify supervisor/leading hand of any defects. (Where defects are of a safety hazard park-up the road sweeper and put an out of service tag on it and discuss hazard with supervisor/foreman. They will have the hazard rectified). 3. Adjust the seat and use the seat belt.	Operator	2
Prior to work commencing	Damage, injury, potential missiles, litigation.	1	1. Operator must be conversant with operation and safety requirements of the machine. 2. Consider risks and hazards in proposed work area to self and others, eg broken glass, debris etc.	Operator	2
Check job site	Damage, injury, potential missiles, litigation.	1	1. Ensure area is free of obstacles, and unnecessary people. 2. If practical - place signs on road to enable adequate warning to public.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Striking personnel and plant on the road worksite	1	1. Hold toolbox meeting to discuss hazards. 2. Reflective safety vests to be worn at all times. 3. Where possible minimise personnel & plant working closely together in work areas. 4. Separate trafficable areas. 5. Install give way and stop signs where necessary. 6. Road sweeper to have operational flashing light and reversing beeper. 7. Two way radios to be used between Road Sweeper and mobile equipment Drivers and Truck Drivers in work areas where it is deemed by the Supervisor to be restricted areas.	Supervisor All Supervisor Supervisor Supervisor Operator	2
Enter vehicle	Injury, fall	2	1. Carefully mount vehicle using steps and handles/handrails as designed and maintain 3 points of contact.	Operator	3
Starting checks	Unsafe working conditions Increased likelihood of accident during operation	1	1. The operator must be seated and in full control of the road sweeper when starting. 2. Check the operation of all of the controls and gauges. 3. Listen and watch for defects. 4. Inspect and test fluid levels & hydraulic functions. 5. Test lights, horn and travel alarm. 6. Ensure if seat belt is provided that it is un-worn. 7. The Operator shall take all due care and attention whilst operating to ensure that no damage occurs to the machine through Operator negligence.	Operator	2
Road Sweeper Operation	Injury, damage	1	1. Before moving vehicle check again that area is clear. 2. Always drive in forward on the job site where practicable. If having to drive in reverse, ensure there is no persons or equipment behind you. 3. Use smooth acceleration, approach job area carefully and slowly – operate machine as per manufacturers specifications and as per operator training. 4. BEWARE OF OBSTACLES AND BYSTANDERS	Operator	2
Lower sweeper brushes	Injury, damage	2	1. Vigilant observation is required in case hidden debris is discovered.	Operator	3
Dismounting sweeper in between tasks	Personal injury or injuries to other persons or plant.	1	1. Ensure park brake is activated. 2. Ensure engine is turned off. 3. Ensure wheel chocks are in place and road sweeper is turned off and tagged out if working on machine.	Operator	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Completing maintenance works.	Personal injury	1	1. Move road sweeper to a position away from the work site. 2. Follow dismounting rules above including chocking the wheels. 3. Remove keys from ignition. 4. Place a lock out danger tag on the steering wheel to alert others that you are working under or behind machine and not to start the road sweeper. (this is very important as persons have been killed doing maintenance on road sweepers when they have not been turned off and tagged out).	Operator	2
Road sweeper shut down	Personnel struck by rolling plant. Damage to other property or sweeper.	1	1. Assess parking area as to site vision for other works in the area (eg traffic situation on roadworks site, avoid parking where vision is blocked). 2. Park on firm, level ground where possible. 3. Park the machine up and down the slope when parking on a grade. 4. Chock wheels if parked on slope. 5. Park in a non operating area. 6. Park away from deep excavations and trenches. 7. Place the hydraulic lock mechanism in the lock position. 8. Idle the engine for gradual cooling before turning it off. 9. Remove the ignition key and secure the machine.	Operator	2
Environmental Issues	Transmission of material off site to public domain eg mud or to main road.	2	1. Where possible endeavor not to park in muddy areas.	Operator	3
	Hydraulic oil spill	3	1. Make sure there is a visual check of all hydraulic hoses is part of your pre start check. 2. Should there be an extensive oil leak- clean it up immediately.	Operator	3
Administration requirements	N/A	-	1. Complete paperwork as required.	Operator	-

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste products will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.