

SAFE WORK METHOD STATEMENT

Persons responsible for supervising, inspecting work, work methods, plant & equipment and tools	Supervisor/Foreman	Date:	
High Risk Construction Work:	MINOR MAINTENANCE OF VEHICLES/PLANT ON WORKSITE	Project:	
SWMS prepared by Patrick Monaghan – Operations Manager and in consultation with management and workers – 2025. SWMS Review Date: August 2026 unless required earlier		Location:	
Approval to use this SWMS: "I certify that the attached SWMS has been reviewed by me, is endorsed for compliance with WorkSafe guidelines and is approved for use"			
<u>John Guy</u> Name	<u>Director - Paneltec Pty Ltd</u> Position	<u>0408 449 023</u> 	<u>31/08/2025 – V11.0</u> Date

RISK MATRIX

Level	Description of Consequence or Impact	Consequence	Likelihood / Probability		
			L <i>Likely</i>	M <i>Moderate</i>	U <i>Unlikely</i>
H (1) <i>(High level of harm)</i>	Potential death, permanent disability or major structural failure/damage. Off-site environmental discharge/release not contained and significant long-term environmental harm.	H (1) <i>(High)</i>	1	1	2
M (2) <i>(Medium level of harm)</i>	Potential temporary disability or minor structural failure/damage. On-site environmental discharge/release contained, minor remediation required, short-term environmental harm.	M (2) <i>(Medium)</i>	1	2	3
L (3) <i>(Low level of harm)</i>	Incident that has the potential to cause persons to require first aid. On-site environmental discharge/release immediately contained, minor level clean up with no short-term environmental harm.	L (3) <i>(Low)</i>	2	3	3
Level	Likelihood / Probability				
Likely	Could happen frequently				
Moderate	Could happen occasionally				
Unlikely	May occur only in exceptional circumstances				

HIERARCHY OF RISK CONTROL

The hierarchy of controls must be applied in the order below for all identified hazards.

Level 1 Eliminate the hazard
Level 2 Substitute the hazard with something safer.
Level 3 Isolate the hazard from people. Reduce the risks through engineering controls.
Level 4 Reduce exposure to the hazard using administrative actions.
Level 5 Use personal protective equipment The control measures that you put in place should be reviewed regularly to make sure they work as planned

ACTIVITY ANALYSIS

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
Training of repair persons	An untrained person is a danger to himself and others	1	1. Make sure all persons conducting repairs are familiar with the type of equipment they are going to use and are trained in the safe use and are able to operate the equipment to the supplier's recommendations. 2. Make sure all persons understand what the hazards associated with the repair works are, why the risks need to be controlled and how the risks are to be controlled. 3. Make sure all persons understand what protective equipment is needed, why it is needed, and how it is to be fitted and used.	Management Supervisor	2
Personal Protective Equipment	Hand, Eye or bodily injuries	2	1. Suitable PPE is to be worn for the task at hand. eg work boots, gloves, eye protection, long pants, long sleeves, sun protection and a hard hat if required by site.		3
Personnel access areas	Struck by other vehicles on site Trip, slip hazards.	1 2	2. Make sure your work area is suitably identified to ensure other vehicles on site are aware of your presence. 3. Clear any obstacles from around all work areas before and as work progresses. 4. Keep pathways clear of trip hazards. 5. No work within 2m of an open trench or shaft unless barricades are in place.	Maintenance or Repair person	2 3
Performing service or repairing plant or equipment	Crushing injuries	2	1. Make sure machine is on level also firm ground. 2. Stop engine. 3. Apply park brake or chock wheels. 4. Personal care must be taken at all times & wearing of appropriate PPE including wearing of approved safety boots. 5. Keep work area clear of bystanders. 6. Keep clear of crush areas on articulated plant, including steering areas, scissor devices and roller scrapper bars. 7. Use lock pins and safety bars before performing any service.	Maintenance or Repair person	3
	Un-authorized use of machine	1	1. Ensure isolation is completed and tag is highly visible.	Maintenance or Repair person	2
	Personal injury if machine is moved while being worked on	1	1. Ensure isolation is completed and tag is highly visible	Maintenance or Repair person	2

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Hand injuries	2	1. Gloves are to be worn when appropriate. 2. Workers to keep eyes on hands.	Maintenance or Repair person	3
	Eye injuries	2	1. Safety glasses or face shield to be worn as required.	Maintenance or Repair person	3
	Sips, trips or falls	2	1. Maintain good housekeeping. 2. Ensure boots are in good condition and clean underneath. 3. Assess area. 4. Look before moving. 5. Keep eyes on path.	Maintenance or Repair person	3
	Noise exposure	1	1. Hearing protection to be worn when using equipment above 85DbA noise levels.	Maintenance or Repair person	2
	Damage to machine or parts	2	1. Consult manufacturer's instructions for repairs, parts or servicing information if unsure.	Maintenance or Repair person	3
	Oil spills / leaks	3	1. All spills to be cleaned up immediately. 2. A tarp is to be placed onto the ground when servicing or conducting maintenance in order to catch any spillage. 3. Ensure no land contamination- use a spill kit or soil if kit not available and dispose of contaminated soil responsibly.	Maintenance or Repair person	3
	Oil splashing into eyes	2	1. Safety glasses to be worn.	Maintenance or Repair person	3
	Overfilling oil	3	1. Oil should not be overfilled	Maintenance or Repair person	3
	Strain injuries / manual handling	2	1. Use two person lifts. 2. Use mechanical devices for heavy lifts.	Maintenance or Repair person	3
	Working in restricted spaces	2	1. Ensure regular breaks are taken.	Maintenance or Repair person	3
	Incorrect use of hand tools	2	1. Ensure correct tool for job. 2. Tools to be checked for damage prior to use.	Maintenance or Repair person	3
	Personal injury from hand tools	2	1. Ensure correct tool for job. 2. Tools to be checked for damage prior to use. 3. Ensure correct PPE is worn for tool.	Maintenance or Repair person	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Machines falling off jacks Injury to person and or plant	1	Before operating Jack 1. Refer to jack instructions. 2. Identify appropriate load bearing point. 3. Make sure jack is in good working order without visible dents or alternations to structure. 4. Make sure appropriate lever is being used and is locked in place. 5. Ensure jacks are securely placed under machines. 6. Put wheel chocks under wheels of the vehicle. 7. Make sure handbrake is turned on. Operation 1. Keep hands and body clear of vehicle and jack mechanism when lifting. 2. Put axle stands in place after car has been jacked up. 3. Do not put any part of the body under the car until the above has been completed POST-Operation: 1. Make sure the area is clear of other people. 2. Take out wheel chocks and axle stands. 3. Slowly lower jack and remove from under car. 4. Return jack, wheel chocks and axle stands to storage area.	Maintenance or Repair person	2
	Cuts, abrasions or bruising	2	1. PPE to be worn at all times. 2. Workers to keep eyes on hands. 3. Assess area. 4. Look before moving. 5. Maintain good housekeeping.	Maintenance or Repair person	3
	Foreign objects imbedded into body parts (eyes, hands, legs etc.)	2	1. PPE to be worn at all times. 2. Workers to keep eyes on hands. 3. Assess area. 4. Look before moving. 5. Maintain good housekeeping.	Maintenance or Repair person	3
	Exposure to various chemicals eg acid, silastic etc	2	1. Read and understand SDS for lubricants and chemicals etc. 2. Exercise extreme care when handling oils and chemicals etc. Use appropriate PPE including gloves and safety glasses or goggles.	Maintenance or Repair person	3

Steps in Activity	Potential Hazards	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class After Controls In Place
	Chemical burns and explosive hazard from contact with lead acid batteries	2	- Exercise extreme care. Lead acid batteries generate explosive gases. - Keep naked flames & fire away. NO SMOKING. Use appropriate PPE including long sleeve buttoned up & long trousers, gloves & approved safety goggles or face shield. Read and understand SDS for lead acid batteries	Maintenance or Repair person	3
	Cuts, lacerations or concussion to head from hitting on trailer while working underneath	2	- Assess area. - Wear PPE.	Maintenance or Repair person	3

ENVIRONMENTAL RISK ASSESSMENT & CONTROL MEASURES THAT MAY BE REQUIRED ON SITE DEPENDING ON THE ACTIVITY					
Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Emergencies	Accident/ Incident Fire Spill	1	1. Personnel have been advised at toolbox meeting and are prepared in the event of an incident occurring. 2. Emergency numbers available on site. 3. Fire Extinguishers/First Aid Kits/Spill Kits on site.	Supervisor All	2
Air Quality	Exhaust Fumes Dust	2	1. Control exhaust emissions eg. Regular maintenance, replace old machinery, fit appropriate emission control measures. 2. Dampen milled surface with water cart. 3. Use water cart where required.	Supervisor All	3
Community Relations	Inconvenience as a result of works/traffic management	2	1. Identify from the list of potentially impacted parties who may be impacted by the work being undertaken. 2. Letter drops could be considered (unless specifically required) to notify residents/businesses etc. about works to be undertaken and if it has an effect on them.	Supervisor All	3
Flora & Fauna	Some works may require the removal of vegetation. Native fauna may be at risk from excavation works	2	1. Assess work area for significant vegetation: size of trees, faunal habitat - define work and exclusion areas using fencing and signage. 2. Machinery is to be thoroughly washed down prior to leaving site where noxious weeds are present.	Supervisor All	3
Heritage & Archaeology	Unmonitored excavation at significant sites can lead to loss or destruction of valuable artifacts/relics, and disturbance of historical sites. including cultural heritage and/or archaeological significance	1	1. Undertake a survey of the site to identify any areas of significance. The client's representative may undertake this. Government bodies may be able to assist. 2. Develop a project specific procedure based on the findings and recommendations. 3. Installation of exclusion fencing and signage if required.	Supervisor All	2
Noise Pollution, Community Relations & Vibration	Sensitivity to noise - to public & fauna	1	1. Work undertaken during "normal" hours where possible. 2. Affected residents notified in person or in writing. 3. Plant and equipment regularly serviced & fitted with efficient mufflers. 4. Magnitude of vibration reduced by using smaller plant etc.	Supervisor All	2

Work Activity Risk	Hazard	Risk Class	Risk Control Measure	Responsible Person/s	Risk Class after Controls in place
Soil Management & Water Quality	Soil needs to be managed to ensure that; there are no off-site impacts. Damage to stockpile areas (not prepared properly). Mud deposited onto roadways.	2	1. Wash down machinery in only nominated areas. 2. Not within 20 metres of water courses. 3. Use only approved and nominated stockpile areas. 4. Build bund wall out of material available on site. 5. Drivers to check vehicle tyres/bodies for build up of mud when leaving stockpile sites and remove if necessary.	Supervisor All	3
Fuels and Chemicals	Contamination of waterways due to spillages of oil, degreasers, diesel, etc.	1	1. Store fuel and chemicals in accordance with relevant standards/guidelines. 2. Minimise storage on site and locate storage facilities away from drains and waterways. 3. All containers clearly labelled and Safety Data Sheets are available on site. 4. All drums stored securely and in a bunded area. 5. Spill kits or alternative spill containment materials available on site. 6. Regular maintenance of plant hoses. 7. Use correct refuelling equipment.	Supervisor All	2
Visual Impact Litter and Amenities Waste Management	Litter such as paper, plastic, and other refuse as well as being a possible safety risk may be carried off-site or washed into waterways resulting in pollution and danger to native fauna. Litter is also visually obtrusive. Production generated lighting, litter, mud, dirt and dust may also impact residents.	2	1. Use site induction to communicate the requirement for a tidy site. Also stress consideration for local residents. 2. If as a result of our works, dirt, mud, or litter affects a resident, then we will rectify this problem immediately. 3. Inspect the site frequently and insist on tidiness. Ensure public roads are free of dirt/mud from the work site. 4. Broken-out paved surfaces shall be repaired as soon as possible. 5. Remove all rubbish from site each day. 6. Waste products will be recycled where possible.	Supervisor All	3

Personal Protective Equipment						
All site personnel must wear the required PPE specified in the controls above, such as:						
Safety Hi-vis Vests/Shirts	Safety Boots	Sunscreen	Broad Brimmed Sun Hat	Sunglasses	Gloves specific to the task	White reflective overalls/night
Hard Hat where required	Safety Glasses	Hearing protection where required	Long clothing	Dust masks	Respiratory equipment if required	
Workers may require Task Specific Training depending on activity each worker will be required to fulfill.						
All workers shall hold a current Construction Induction Card						
- If required Client Site Induction - Activity Induction (SWMS & SWP's)	Vehicle Licences (Car or Truck depending on class of vehicle or mobile plant driven)		Plant Operators licences or competency assessments where required		Competencies for Work Zone Traffic Management	
First Aid certificate training	Manual Handling training		Fire Extinguisher training		Fatigue Management Training	
A Site Specific Induction & Toolbox Meeting will be held each day prior to the start of each job.						
Legislation & Codes of Practice (refer to company Legislation register for applicable Australian Standards applicable to works)						
Work Health & Safety Act 2012 and Work Health & Safety Regulations 2022						
Codes of Practice						
Confined Spaces - 2020	Hazardous Manual Tasks - 2020	Managing Noise & Preventing Hearing Loss at Work-2020		Managing Risks of Plant in the Workplace - 2018		
Construction Work - 2020	How to Manage WH&S Risks - 2018	Managing Risk of Falls at Workplaces - 2020		Managing Electrical Risks in the Workplace -2019		
Excavation Work - 2020	First Aid in the Workplace - 2018	Managing Work Environment & Facilities - 2020		WHS Consultation Co-operation & Co-ordination - 2018		
Welding Processes - 2021	How to Safely Remove Asbestos - 2020	Managing Risk of Hazardous Chemicals - 2018		Safe Design of Structures - 2018		
Plant & Equipment for this activity						
- All plant is inspected prior to sending out to site - Daily maintenance & service checks. - Daily pre-start checks are conducted on all plant and trucks by the operators and daily checklist filled out. - Regular servicing at 250hr intervals or as per manufactures specifications. Service History available on request to the office.						
List of plant for this Activity						
Engineering details/certificates/regulatory approvals/permits/electrical isolation (if applicable):						

Implementation, Monitoring and Review of SWMS

The Supervisor on site has the responsibility to:

- Brief each team member on this SWMS before commencing work.
- Ensure control measures have been implemented prior to the start of works.
- Observe work being carried out.
- If controls documented in SWMS are not adequate, stop the work, review the SWMS, adjust as required and re-brief the team.
- Ensure team knows that work is to immediately stop if the SWMS is not being followed.
- Retain this SWMS on site for the duration of the high-risk construction work.
- All persons involved in these particular tasks on site must sign this document as read and understood.

SWMS attendance sheet — I have been given the opportunity to provide input into the development and review of this SWMS

Name (please print clearly)	Signature	Company	Date

Daily pre-start meetings will be held to ensure all workers are informed of control measures and additional safety hazards & controls to be noted on toolbox form.